BENGALURU SOLID WASTE MANAGEMENT LIMITED

TENDER DOCUMENT – KW4

(WORKS COSTING MORE THAN Rs.1000 LAKHS)

Name of Work - Village development works in Yeshwanthapura constituency around Seegehalli, Kannahalli & Doddabidrakallu waste processing plants.
Village development works in Anekal & Bengaluru South constituency around waste Chikkanagamangala waste processing plant.
Village development works in Yeshwanthapura constituency around Subbarayanapalya, Lingadheeranhalli waste processing plants.

BENGALURU SOLID WASTE MANAGEMENT LIMITED

Office of the Deputy General Manager-2, 1st Floor, UNI Building, Thimmaiah Road, Vasanth Nagar, Bengaluru–560 052.

Phone No: 6362975012

TENDERS FOR THE WORK OF

Sl No	Name of Work	Value of Work (in Lakhs)
1	Village development works in Yeshwanthapura constituency around Seegehalli, Kannahalli & Doddabidrakallu waste processing plants. Village development works in Anekal & Bengaluru South constituency around waste Chikkanagamangala waste processing plant. Village development works in Yeshwanthapura constituency around Subbarayanapalya, Lingadheeranhalli waste processing plants.	5956.23

TENDER REFERENCE	No. DGM-2/BSWML/Tend/04/24-25, Date:09.09.2024
LAST DATE FOR SALE OF TENDER DOCUMENT	up to 04.10.2024 on or before 4.00 PM
PRE-BID MEETING WILL BE HELD ON	24.09.2024 at 3.00 PM
LAST DATE AND TIME FOR RECEIPT OF TENDERS	04.10.2024 on or before 4.00 PM
TIME AND DATE OF OPENING OF COVER ONE OF TENDERS	05.10.2024 at 4.30 PM
PLACE OF PRE-BID MEETING WILL BE HELD	Office of the Chief Engineer & Chief General Manager (Tech),BSWML, 1st Floor, UNI Building, Thimmaiah Road, Bengaluru-560052.
TIME AND DATE OF OPENING OF COVER TWO OF TENDERS	Will be intimated to the Qualified Tenderers
PLACE OF OPENING OF COVER TWO OF TENDERS AND ADDRESS FOR COMMUNICATION:	Office of the Chief Engineer & Chief General Manager (Tech), BSWML, 1st Floor,UNI Building, Thimmaiah Road, Bengaluru-560052.
	Off: Phone Mob: +91 6362975012

Contents

Section No.	Description	Page
1	INVITATION FOR TENDERS (IFT)	3-6
2	INSTRUCTIONS TO TENDERERS (ITT)	7-17
3.	QUALIFICATION INFORMATION	18-21
4.	FORM OF TENDER, LETTER OF ACCEPTANCE, NOTICE TO PROCEED WITH THE WORK AND AGREEMENT FORM	22-25
5.	CONDITIONS OF CONTRACT (CC)	25-33
6.	CONTRACT DATA	38-38
7	SPECIFICATIONS	39-40
8	DRAWINGS	40-40
9.	BILL OF QUANTITIES	41-72
10.	FORMAT OF BANK GUARANTEE FOR SECURITY DEPOSIT	73-73

SECTION 1: INVITATION FOR TENDERS (IFT)

BENGALURU SOLID WASTE MANAGEMENT

Office of the Deputy General Manager-2, 1st Floor, UNI Building, Thimmaiah Road, Bengaluru-560052.

****

No. DGM-2/BSWML/Tend/04/24-25 Date:09.09.2024

INVITATION FOR SHORT TERM TENDER (IFT)

(Through GOK KPPP only)

1. The Deputy General Manager-2, Bengaluru Solid Waste Management Limited on behalf of the Managing Director, BSWML, Bengaluru from eligible bidders for the works detailed in the table below. The Bidders may submit tenders for works given in the table through KPPP portal of the Government of Karnataka (viz. https://kppp.karnataka.gov.in) The Bidders are advised to note the minimum qualification criteria specified in Clause 3 of the instructions to bidders to qualify for award of the contract.
2. Tender documents may be downloaded from the e-procurement portal of the Government of Karnataka.
3. Other details can be seen in the tender documents.

Sl No.	Name of the work	Amount put to tender (Rs. in lakhs) Excluding GST	EMD (Amount in Rs)	Cost of Tender Document	Contract completion period
1	Establishment of New landfill site at Mittaganahalli and Kannuru (Balance portion) and development of surrounding villages by creating required infrastructure in Mahadevapura Constituency. Village development works in Mahadevapura constituency around Mandur legacy waste Bio-Mining site.	7147.79	Rs.1,00,000/- through e-payment under of the following i.e., online / RTGS / NEFT / OTC and the balance Rs.70,50,000/- by Bank Guarantee/FDR issued by Nationalized/Scheduled Bank	As per KPPP portal	12 Months

2	Development of Approach Roads to at Mittiganahalli and Kannuru Landfill surroundings in Mahadevapura Constituency	3971.19	Rs.1,00,000/- through e-payment under of the following i.e., online / RTGS / NEFT / OTC and the balance Rs.38,72,000/- by Bank Guarantee/FDR issued by Nationalized/Scheduled Bank	As per KPPP portal	9 Months
3	Establishment and development of new landfill site at Baiyappanahalli Sy No.80, Pit No.2 of North side including O & M in Byatarayanapura Constituency.	1985.53	Rs.1,00,000/- through e-payment under of the following i.e., online / RTGS / NEFT / OTC and the balance Rs.18,90,000/- by Bank Guarantee/FDR issued by Nationalized/Scheduled Bank	As per KPPP portal	6 Months
4	Providing basic infrastructures and Development of villages around scientific landfills such as Srinivasapura, Sathanuru, Hosahalli, Madakepalya, Kannur, Bande Bommasandra, Chikkagubbi, Kadusoppanahalli, Hosur Bande, Mittaganahalli and other surroudings villages in Byatarayanapura and Mahadevapura Constituency.	1985.62	Rs.1,00,000/- through e-payment under of the following i.e., online / RTGS / NEFT / OTC and the balance Rs.18,90,000/- by Bank Guarantee/FDR issued by Nationalized/Scheduled Bank	As per KPPP portal	6 Months

5	Village development works in Yeshwanthapura constituency around Seegehalli, Kannahalli & Doddabidrakallu waste processing plants. Village development works in Anekal & Bengaluru South constituency around waste Chikkanagamangala waste processing plant. Village development works in Yeshwanthapura constituency around Subbarayanapalya, Lingadheeranhalli waste processing plants.	5956.23	Rs.1,00,000/- through e-payment under of the following i.e., online / RTGS / NEFT / OTC and the balance Rs.59,00,000/- by Bank Guarantee/FDR issued by Nationalized/Scheduled Bank	As per KPPP portal	12 Months
6	Establishment of New scientific landfill site in available quarry pit (Balance portion Phase-2) at Bayyappanahalli Sy. No. 80 and development of surrounding villages by creating required infrastructure in Byatarayanapura Constituency.	7148.32	Rs.1,00,000/- through e-payment under of the following i.e., online / RTGS / NEFT / OTC and the balance Rs.70,50,000/- by Bank Guarantee/FDR issued by Nationalized/Scheduled Bank	As per KPPP portal	11 Months

Note:

1. Pre bid meeting will be held on 24-09-2024 at 15:00 hours in office of the Chief Engineer & Chief General Manager (tech), BSWML, UNI Building, Thimmaiah Road, Vasanth Nagar, Bengaluru - 52.
2. Technical Documents along with necessary information/documents must be uploaded to the KPPP portal https://kppp.karnataka.gov.in as per tender document on or before 16:00 hours on 04-10-2024 and First Folder containing the Technical bid will be opened through e-portal only on 05-10-2024 after 16:30 hours at the stipulated venue, in the presence of the Tenderers or their authorized representatives who wish to attend. If the office happens to be closed on the date of opening of the tenders as specified, the tenders will be opened on the next working day at the same time and venue.
3. The Employer shall not be liable for any delays due to system failure beyond its control. Even though the system will attempt to notify the Tenderers of any tender updates, the Employer shall not be liable for any information not received by the Tenderers. It is the Tenderers responsibility to verify the KPPP portal for the latest information related to the tender, E-mail address of the Helpdesk is hphelpdesk.blr@intarvo.com. KPPP portal help desk telephone

numbers are: 080-22371090/22373788. The tenderer is required to ensure browser capability of the computer well in advance to the last date and time for receipt of the tenders. The employer shall not be responsible for non-accessibility of KPPP portal due to internet connectivity issues and technical glitches.

4. Any corrigendum/addendum will be published in the KPPP portal only.

Sd/-
Deputy General Manager-2
BSWML

Copy Submitted to the:

1. Hon'ble Chairman, BSWML & ACS, UDD for kind information.
2. Hon'ble Managing Director, BSWML/Chief Commissioner, BBMP for kind information.
3. Chief Executive Officer, BSWML /Special Commissioner, SWM, BBMP for kind information.
4. Chief Operational Officer BSWML, for kind information.
5. Chief Financial officer BSWML /CAO, BBMP for kind information.
6. Chief Engineer & Chief General Manager(Tech) BSWML/CE (SWM), BBMP for kind information
7. Company Secretary, BSWML for kind necessary action.
8. Office Copy

Deputy General Manager-2
BSWML

SECTION 2: INSTRUCTIONS TO TENDERERS (ITT)

Table of Clauses

			Page No.
A.	**General**		
	1.	Scope of Tender	8
	2.	Eligible Tenderers	8
	3.	Qualification of the Tenderer	8
	4.	One Tender per Tenderer	10
	5.	Cost of Tendering	10
	6.	Site Visit	10
B.	**Tender Documents**		
	7.	Content of Tender documents	10
	8.	Clarification of Tender Document	10
	9.	Amendment of Tender documents	10
C.	**Preparation of Tenders**		
	10.	Documents comprising the Tender	11
	11.	Tender prices	11
	12.	Tender validity	11
	13.	Earnest money deposit	12
	14.	Format and signing of Tender	12
D.	**Submission of Tenders**		
	15.	Sealing and marking of Tenders	12
	16.	Deadline for submission of Tenders	13
	17.	Late Tenders	13
	18.	Modification and Withdrawal of Tenders	13
E.	**Tender opening and evaluation**		
	19.	Opening of First Cover of all Tenders and evaluation to determine qualified Tenderers	13
	20.	Opening of Second Cover Tenders of qualified Tenders and evaluation	14
	21.	Process to be confidential	14
	22.	Clarification of Tenders	14
	23.	Examination of Tenders and determination of responsiveness	14
	24.	Correction of errors	14
	25.	Evaluation and comparison of Tenders	15
F.	**Award of contract**		
	26.	Award criteria	15
	27.	Employer‟s right to accept any Tender and to reject any or all Tenders	15
	28.	Notification of award and signing of Agreement	15
	29.	Security deposit	16
	30.	Advance payment and Security	16
	31	Corrupt or Fraudulent Practices	16

A. General

1. Scope of Tender

The Deputy General Manager-2, BSWML, on behalf of the Managing Director, BSWML (Referred to as Employer in these documents) invites ITEM RATE tenders following Two Cover tender procedure, from eligible Tenderers, for the works of "Village development works in Yeshwanthapura constituency around Seegehalli, Kannahalli & Doddabidrakallu waste processing plants.Village development works in Anekal & Bengaluru South constituency around waste Chikkanagamangala waste processing plant.Village development works in Yeshwanthapura constituency around Subbarayanapalya, Lingadheeranhalli waste processing plants." (as defined in these documents and referred to as "the works") detailed in the Table given in the Invitation for Tenders (IFT). The Tenderers may submit tenders for any or all of the works detailed in the table given in IFT.

2. Eligible Tenderers

Tenderers shall not be under a declaration of ineligibility for corrupt and fraudulent practices issued by theGovernment of Karnataka/BBMP. A Bidder shall be any individual, Firm, Agency registered BBMP, BDA, NH, PWD, CPWD or other central/state agencies with qualification as set forth in clause 3 below.

Tenders from Joint ventures are not acceptable.

3. Qualification of the Tenderer:

All Tenderers shall provide the requested information accurately and in sufficient detail in Section 3: Qualificationinformation.
To qualify for award of this contract, each Tenderer in its name should have in the last five financial years (i.e. **2019-20 to 2023-24**)

(a) Achieved in at least two financial years a minimum financial turnover (in all classes of Civil works) of **Rs.11912.46 lakhs**

(b) Mandating satisfactorily completion as a prime contractor, at least one similar nature of work in works to as extent of 50% of the cost of the work **(Rs.2978.12 lakhs)**

(c) executed in any one financial year, the following minimum quantities of work: (usually 80% of the peak annualrate of construction)

SL No	Item	Unit	Qty
1	Earthwork Excavation	Cum	42936.00
2	Cement Concrete in all grade	Cum	5138.00
3	TMT Steel	Tonne	169.00
4	GSB	Cum	14321.00
5	Constructions of Dry Lean Concrete	Cum	1358.00
6	WMM	Cum	18417.00
7	DBM	Cum	5255.00
8	BC	Cum	4135.00
9	Supplying preparation & spraying of lemon grass	Litres	2150400.00
10	Providing bio product solutions	Litres	2469600.00
11	100mm Precast Cover slab	Sqm	4388

(d) Deleted

(e) Deleted

Each Tenderer should further demonstrate:

(a) Availability by owning at least 50% of the required / specified key and critical equipment for this work and the remaining 50% can be deployed on lease / hire basis for all works provided the relevant documents (commitment

agreements etc.) for availability for this work are furnished.

Sl No	Descriptions	Nos	Own/Lease
1	Hot Mix Plant (Minimum capacity of 40/60 TPH)	1	Own
2	Mechanical paver finisher	2	Own
3	Vibratory roller	2	Own
4	Static road roller	2	50% Own/ 50% lease
5	Tippers	12	50% Own/ 50% lease
6	Excavators like JCB/Hitachi	10	50% Own/ 50% lease
7	Water tanker	4	50% Own/ 50% lease

(b) Liquid assets and /or availability of credit facilities of not less than Rs.**1786.87** Lakhs (Credit lines/ letter of credit/ certificates from banks for meeting the fund requirement etc.

To qualify for a package of contracts made up of this and other contracts for which tenders are invited in this IFT, the Tenderer must demonstrate having experience and resources to meet the aggregate of the qualifying criteria for the individual contracts.
Sub-contractors‟ experience and resources shall not be taken into account in determining the Tenderer's compliance with the qualifying criteria except to the extent stated in 3.2 (d) and (e) above.
Tenderers who meet the above specified minimum qualifying criteria, will only be qualified, if their available tender capacity is more than the total tender value. The available tender capacity will be calculated as under:

Assessed available tender capacity = (A*N*1.5 - B)

Where

A = Maximum Value of Civil Engineering Works executed in any One Year during the last Five years **(updated to 2024-25 Price Level)** taking into account the Completed as well as Works in Progress.
N = Number of years prescribed for Completion of the Works for which Tenders are Invited i.e. 12 Months.
B = Value, at **2024-2025 Price Level on 10% Weightage per annum**, of Existing Commitments and on Going Works to be completed during the next 12 months including Monsoon Season.

Note: The statements showing the value of existing commitments and on-going works as well as the stipulated period of completion remaining for each of the works listed should be countersigned by the Employer in charge, not below the rank of an Executive Engineer or equivalent.

Even though the Tenderers meet the above criteria, they are subject to be disqualified if they have:

- made misleading or false representations in the forms, statements and attachments submitted in proof of the qualification requirements; and/or
- record of poor performance such as abandoning the works, not properly completing the contract, inordinate delays in completion, litigation history, or financial failures etc.; and/or
- Participated in the previous Tender for the same work and had quoted unreasonably high tender prices and could not furnish rational justification.

4. One Tender per Tenderer

Each tenderer shall submit only one tender for one package. A tenderer who submits or participates in more than one Tender (other than as a sub-contractor or in cases of alternatives that have been permitted or requested) will cause all the proposals with the Tenderer's participation to be disqualified.

5. Cost of Tendering:

The tenderer shall bear all costs associated with the preparation and submission of his tender, and the Employer will in no case be responsible and liable for those costs.

6. Site visit:

The Tenderer at his own responsibility and risk is encouraged to visit and examine the Site of Works and its surroundings and obtain all information that may be necessary for preparing the Tender and entering into a contract

for construction of the Works. The cost of visiting the Site shall be at the Tenderer‟s own expense.

B. Tender documents

7. Content of Tender documents

The set of tender documents shall have all the Sections given in Page **3**
Both the sets should be completed and returned with the tender.

8. Clarification of Tender Documents

A prospective tenderer requiring any clarification of the tender documents may notify the Employer in writing or by cable (hereinafter "cable" includes telex and facsimile) at the Employer's address indicated in the invitation to tender. The Employer will respond to any request for clarification which he receives earlier than 15 days prior to thedeadline for submission of tenders. Copies of the Employer's response will be forwarded to all purchasers of the tender documents, including a description of the enquiry but without identifying its source.

Pre-tender meeting:

The tenderer or his authorized representative is invited to attend a pre-tender meeting which will take place at Office of the Office of the Chief Engineer & Chief General Manager (Tech), BSWML, 1st Floor, UNI Building, Thimmaiah Road, Bengaluru-560052 **on 24.09.2024 at 3.00 PM.**
The purpose of the meeting will be to clarify issues and to answer questions on any matter that may be raised at that stage.
The tenderer is requested to submit any questions in writing or by cable to reach the Employer not later than **24.09.2024 at 4.00PM.**
Minutes of the meeting, including the text of the questions raised (without identifying the source of enquiry) and the responses given will be transmitted without delay to all purchasers of the tender documents. Any modification of the tender documents listed in Sub-Clause 7.1 which may become necessary as a result of the pre-tender meeting shall be made by the Employer exclusively through the issue of an Addendum pursuant to Clause 9 and not through the minutes of the pre-tender meeting.
Non-attendance at the pre-tender meeting will not be a cause for disqualification of a tenderer.

9. Amendment of Tender documents

Before the deadline for submission of tenders, the Employer may modify the tender documents by issuing addenda.
Any addendum thus issued shall be part of the tender documents and shall be communicated in writing or by cable to all the purchasers of the tender documents.
To give prospective Tenderers reasonable time in which to take an addendum into account in preparing their tenders, the Employer shall extend as necessary the deadline for submission of tenders, in accordance with Sub-Clause 16.2 below

C. Preparation of Tenders

10. Documents comprising the Tender

The tender submitted by the Tenderer shall be in two covers and shall contain the documents as follows:

First Cover:
(a) Earnest Money Deposit;
(b) Qualification Information as per formats given in Section 3;

Second Cover:

(a) The Tender (in the format indicated in Section 4)
(b) Priced Bill of Quantities (Section 9);
and any other materials required to be completed and submitted by Tenderers in accordance with these instructions.

The documents listed under Sections 3, 4, 6 and 9 shall be filled in without exception.
Tenderers submitting tenders together with other contracts stated in the IFT to form a package will so indicate in the tender together with any discounts offered for the award of more than one contract.

11. Tender prices

The contract shall be for the whole works as described in Sub-Clause 1.1, based on the priced Bill of Quantities submitted by the Tenderer.
The Tenderer shall fill in rates and prices and line-item total (both in figures and words) for all items of the Works described in the Bill of Quantities along with total tender price (both in figures and words). **Items for which no rate or price is entered by the Tenderer will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of Quantities**. Corrections, if any, shall be made by crossing out, initialing, dating and rewriting.
All duties, taxes, and other levies payable by the contractor under the contract, or for any other cause, shall be included in the rates, prices and total Tender Price submitted by the Tenderer.
The rates and prices quoted by the Tenderer shall be subject to adjustment during the performance of the Contract in accordance with the provisions of Clause of the Conditions of Contract

12. Tender validity

Tenders shall remain valid for a period not less than **One Hindered and Eighty days (180)** after the deadline date for tender submission specified in Clause 16. A tender valid for a shorter period shall be rejected by the Employer as non-responsive.

In exceptional circumstances, prior to expiry of the original time limit, the Employer may request that the Tenderers may extend the period of validity for a specified additional period. The request and the Tenderers' responses shall be made in writing or by cable. A Tenderer may refuse the request without forfeiting his earnest money deposit. A Tenderer agreeing to the request will not be required or permitted to modify his tender, but will be required to extend the validity of his earnest money deposit for a period of the extension, and in compliance with Clause 13 in all respects.

13. Earnest money deposit

The Tenderer shall furnish, as part of his tender, Earnest Money Deposit (EMD) in the amount as mentioned in IFT for this particular Work. Further, out of the total EMD Amount only Rs. 1.00 Lakh (RupEEs One Lakh only) shall be paid in the KPP portal using any of the following modes and the Balance Amount shall be in the form of Bank Guarantee from any Bank.

- Credit Card.
- Direct Debit.
- National Electronic Fund Transfer (NEFT).
- Over the Counter (OTC).

NEFT Payment Procedure:

If a Tenderer chooses to make Payment of EMD / Tender Processing FEE using Reserve Bank of India's (RBI) National Electronic Fund Transfer (NEFT) System, the Tenderer will need to log into KPPP System, access the Tender for which Bid is being created and then select the NEFT Option under the Payment Section and print the Challan shown in that Section. The Printed Challan will have the Unique Bid Reference Number, Account Details of Government of Karnataka and the Amount to be remitted. The Tenderer shall submit the Printed Challan to its Bank Branch (NEFT enabled) and request foran Account – to – Account Transfer, wherein the money will get transferred from the Tenderer's Bank Account to GOK"s Bank Account. The Tenderer shall ensure that NEFT Transfer Instructions are executed and the Funds are wired to the Government of Karnataka's Principal Account before the Last Date for Bid Submission and preferably 24 hours before the Last Date for Bid Submission. If the Tenderer's Bank transfers / wires the money after the Last Date for Bid Submission, the Tenderer's Bid will be liable for rejection. Upon executing the Transfer, the Tenderer's Bank will provide a Reference Number generated by NEFT Software as Confirmation of Transfer, which has to be input by the Tenderer in the Payment Section of its Bid as Payment Confirmation before the Bid is submitted i.e. as a pre requisite for Bid Submission. The Account Number from which the Funds were transferred shall be input in the KPPP System as part of its Bid also.

OTC Payment Procedure:

If a Tenderer chooses to make Payment of EMD / Tender Processing FEEs Over The Counter (OTC) in any of the designated Axis Bank Branches listed in the KPPP Website (www.kppp.karnataka.gov.in), the Tenderer will need to log intoKPPP System, access the Tender for which Bid is being created and then select the OTC Option under the PaymentSection and print the Challan shown in that Section. The Printed Challan will have the Unique Bid Reference Number andthe Amount to be remitted along with the Challan. The Tenderer can choose to make the Payment either in the form of Cash or in the form of Demand Draft. Cheque Payments will not be accepted. The Tenderer is requested to specifically inform the Bank Officer to input the Unique Bid Reference Number printed in the Challan in the Banking Software. Upon successful Receipt of the Payment, the Bank will provide a 16 Digit Reference Number acknowledging the Receipt of Payment. This 16 Digit Reference Number has to be input by the Tenderer in the Payment Section of its Bid as Payment Confirmation before the Bid is submitted i.e. as a pre requisite for Bid Submission.

The Tenderer shall furnish, as part of his tender, earnest money deposit (EMD) at the following rates
a) Up to Rs.20 Lakhs - 2.5%
b) Rs.20 Lakhs and above up to Rs. 1 crore – 2% subject to a minimum of Rs. 50,000/-
c) Rs.1 crore and above up to Rs.10 crores – 1% subject to a minimum of Rs. 2,00,000/-
d) Rs.10 crores and above – 1% subject to a minimum of Rs.15,00,000/-.

e) Fixed Deposit Receipt (FDR) subject to the following condition

- Maturity date of FDRs issued by the Bank should be beyond the date expected date of finalization of the tender.

Earnest money deposit will have to be in any one of the forms as specified in the Tender document and as per circular PWD:15:ITC:2008/2009 Dated:02-12-2010 (Minimum of Rs.1,00,000/- through e-payment under of the following i.e., online / RTGS / NEFT / OTC and the balance by bank guarantee/FDR issued by Nationalized/ Scheduled Bank and shall have to be valid for 90 days beyond the validity of the tender.
Instruments having fixed validity issued as earnest money deposit for the tender shall be valid for 90 days **beyond** the validity of the tender.
Any tender not accompanied by an acceptable earnest money deposit and not secured as indicated in Sub-Clauses 13.1 and 13.2 above shall be rejected by the Employer as non-responsive.
The earnest money deposit of unsuccessful Tenderers will be returned within 30 days of the end of the tender validity period specified in Sub-Clause 12.1.
The earnest money deposit of the successful Tenderer will be discharged when the Tenderer has signed the Agreement and furnished the required Performance Security.

The earnest money deposit may be forfeited:
(a) if the Tenderer withdraws the Tender after tender opening during the period of tender validity;
(b) if the Tenderer does not accept the correction of the Tender Price, pursuant to Clause 24; or
(c) in the case of a successful Tenderer, if the Tenderer fails within the specified time limit to
(i)sign the Agreement; or
(ii) furnish the required Security deposit

14. Format and signing of Tender

Tenderer shall submit the Bid electronically before the submission date and time published in kpp portal.

D. Submission of Tenders

15. Sealing and marking of tenders

Tenderer shall submit the Tender document electronically before the submission date and time published. The document for submission shall be uploaded in PDF format and submitted in the order mentioned below.

1. Content sheet with name of folder / file, No of pages in each folder / file and size of the folder/file.

FIRST COVER /FOLDER (TECHNICAL PART)
2. As per Section 3 - Qualification information
a. Qualification information summary sheets
b. Affidavit as per the format attached in qualification information.

c. Brief description of tenderer with the details of contact person for communication with BSWML
d. Attested copy of Registration certificate of the contractor
e. EMD as specified in the Table of I TT in the document.
f. Power of attorney for signing the tender as per the format attached in qualification information.
g. Work performed & quantity executed as per Table with supporting certificates from client for the claims mentioned in tables of qualification information.
h. Tables Qualification information with supporting certificate from client &calculation sheet for available tender capacity.
i. Availability of machinery as per Table of qualification information.
j. Experience & qualification of key persons as per Table of qualification information.
k. Financial statement for past five F.Y, contains balance sheet, profit& loss, statement on cash on hand, liquid assets etc from Charted Accountant.
l. Line of credit and details of tenderers bank with reference as per format attached in qualification information.
n. Litigation history as per Table. Of qualification information.
o. Method adopted for construction program, bar chart, quality assurance program as per clause 1.13 of qualification information
p. Undertaking for the tender is valid for 180 days as per clause 1.14 of qualification information.

SECOND COVER/FOLDER (FINANCIAL PART)

a. Form of tender as per section 4 (I) of tender document.
b. Priced Bill of Quantity.
c. Any other materials required to be completed and submitted by Tenderers in accordance with ITT.

Deleted
Deleted

16. Deadline for submission of the Tenders

Tenders must be received by the Employer at the address specified above no later than **4.00PM hours on 04.10.2024**
In the event of the specified date for the submission of tenders being declared a holiday for the Employer, the tenders will be received up to the appointed time on the next working day.
The Employer may extend the deadline for submission of tenders by issuing an amendment in accordance with Clause 9, in which case all rights and obligations of the Employer and the Tenderers previously subject to the original deadline will then be subject to the new deadline.

17. Late Tenders

Any Tender received by the Employer after the deadline prescribed in Clause 16 will be returned unopened to the Tenderer.

18. Modification and Withdrawal of Tenders

Tenderers may modify contents of First or Second Covers separately for each Cover or withdraw their Tenders by giving notice in writing before the deadline prescribed in Clause 16.
Each Tenderer's modification separately for each Cover or withdrawal notice shall be prepared, sealed, marked, and delivered in accordance with Clause 14 & 15, with the outer and inner envelopes additionally marked "**MODIFICATION FOR FIRST/SECOND COVER**" or "**WITHDRAWAL**", as appropriate.
No Tender may be modified after the deadline for submission of Tenders.
Withdrawal or modification of a Tender between the deadline for submission of Tenders and the expiration of the original period of Tender validity specified in Clause 12.1 above or as extended pursuant to Clause 12.2 may result in the forfeiture of the earnest money deposit pursuant to Clause 13.
1 8.5 Tenderers may only offer discounts to, or otherwise modify the prices of their Tenders by submitting Tender modifications in accordance with this clause, or included in the original Tender submission.

E. Tender opening and evaluation

19. Opening of First Cover of all Tenders and evaluation to determine qualified Tenderers:

The Employer will open the First Covers of all the Tenders received (except those received late or withdrawn), including modifications for First Cover made pursuant to Clause 18, in the presence of the Tenderers or their representatives who

choose to attend at 05.10.2024 at 4.30 PM on the date and the place specified in Clause 16. In the event of the specified date of Tender opening being declared a holiday for the Employer, the Tenders will be opened at the appointed time and location on the next working day.

Deleted

The Tenderers names, the presence or absence of earnest money deposit (amount, format and validity), the submission of qualification information and such other information as the Employer may consider appropriate will be announced by the Employer at the opening.

The Employer shall prepare minutes of the Tender opening, including the information disclosed to those present in accordance with Sub-Clause 19.3.

Deleted

The Employer will evaluate and determine whether each tender

(a) meets the eligibility criteria defined in ITT Clause 2;

(b) is accompanied by the required earnest money deposit as per stipulations in ITT Clause and

(c) Meets the minimum qualification criteria stipulated in ITT Clause 3. The Employer will draw out a list of qualified Tenderers.[2]

20. Opening of Second Cover of qualified Tenderers and evaluation:

The Employer will inform all the Qualified Tenderers the time, date and venue fixed for the opening of the Second Cover containing the priced Tenders. The Employer will open the Second Covers of Qualified Tenderers at the Appointed time and date(as indicated in the KPP portal) in the presence of the Tenders or their representatives who choose to attend. In the event of the specified date of Second Cover opening being declared a holiday for the Employer, the Second Covers will be opened at the appointed time and location on the next working day.

Deleted

Deleted

The Employer shall prepare minutes of the Second Cover Tender opening.

21. Process to be confidential

Information relating to the examination, clarification, evaluation, and comparison of Tenders and recommendations for the award of a contract shall not be disclosed to Tenderers or any other persons not officially concerned with such process until the award to the successful Tenderer has been announced. Any effort by a Tenderer to influence the Employer's processing of Tenders or award decisions may result in the rejection of his Tender.

22 Clarification of Tenders

To assist in the examination, evaluation, and comparison of Tenders, the Employer may, at his discretion, ask any Tenderer for clarification of his Tender, including breakdowns of unit rates. The request for clarification and the response shall be in writing or by cable, but no change in the price or substance of the Tender shall be sought, offered, or permitted except as required to confirm the correction of arithmetic errors discovered by the Employer in the evaluation of the Tenders in accordance with Clause 24.

Subject to sub-clause 22.1, no Tenderer shall contact the Employer on any matter relating to its Tender from the time of the Tender opening to the time the contract is awarded. If the Tenderer wishes to bring additional information to the notice of the Employer, it should do so in writing.

Any effort by the Tenderer to influence the Employer in the Employer’s Tender evaluation, Tender comparison or contract award decisions may result in the rejection of the Tenderers‟ Tender.

23. Examination of Tenders and determination of responsiveness

Prior to the detailed evaluation of Tenders, the Employer will determine whether each Tender;

(a) has been properly signed; and;

(b) is substantially responsive to the requirements of the Tender documents.

A substantially responsive Tender is one which conforms to all the terms, conditions, and specifications of the Tender documents, without material deviation or reservation. A material deviation or reservation is one

(a) which affects in any substantial way the scope, quality, or performance of the Works;

(b) which limits in any substantial way, inconsistent with the Tender documents, the Employer's rights or the Tenderer's obligations under the Contract; or

(c) whose rectification would affect unfairly the competitive position of other Tenderers presenting substantially responsive Tenders.

If a Tender is not substantially responsive, it will be rejected by the Employer, and may not subsequently be made responsive by correction or withdrawal of the nonconforming deviation or reservation.

24. Correction of errors

The Tenderer may modify the tender only before the last date for submission of the tender, as indicated on the KPP portal.

25. Evaluation and comparison of Tenders

The Employer will evaluate and compare only the Tenders determined to be substantially responsive in accordance with Clause 23.
Deleted (Since Bids submitted online only)
The Employer reserves the right to accept or reject any variation, deviation, or alternative offer. Variations,deviations, and alternative offers and other factors which are in excess of the requirements of the Tender documents or otherwise result in unsolicited benefits for the Employer shall not be taken into account in Tender evaluation.

The estimated effect of the price adjustment conditions under Clause 41 of the Conditions of Contract, during the implementation of the Contract, will not be taken into account in tender Evaluation
If the tender of the successful tenderer is seriously unbalanced in relation to the Employer's estimate of the cost of the work to be performed under the contract, the Employer may require the Tenderer to produce detailed price analyses for any or all items of the Bill of Quantities, to demonstrate the internal consistency of those prices with theconstruction methods and schedule proposed. After evaluation of the price analyses, the Employer may require that the amount of the performance security set forth in Clause 29 be increased at the expense of the successful Tenderer to a level sufficient to protect the Employer against financial loss in the event of default of the successful under the contract.

F. Award of Contract

26. Award criteria

Subject to Clause 27, the Employer will award the Contract to the Tenderer whose Tender has been determined to be substantially responsive to the Tender documents and who has offered the lowest evaluated Tender Price, provided that such Tenderer has been determined to be

(a) eligible in accordance with the provisions of Clause 2, and
(b) Qualified in accordance with the provisions of Clause 3.

27. Employer's right to accept any Tender and to reject any or all Tenders

Not with standing Clause 26, the Employer reserves the right to accept or reject any Tender, and to cancel the Tender process and reject all Tenders, at any time prior to the award of Contract, without thereby incurring any liability to the affected Tenderer or Tenderers or any obligation to inform the affected Tenderer or Tenderers of the grounds forthe Employer's action.

28. Notification of award and signing of Agreement:-

The Tenderer whose Tender has been accepted will be notified of the award by the Employer prior to expiration of the Tender validity period by cable, telex, e-mail or facsimile confirmed by registered letter. This letter (hereinafter and in the *Conditions of Contract* called the "Letter of Acceptance") will state the sum that the Employer will pay the Contractor in consideration of the execution, completion, and maintenance of the Works by the Contractor as prescribed by the Contract (hereinafter and in the Contract called the "Contract Price").
The notification of award will constitute the formation of the Contract, subject only to the furnishing of Security deposit in accordance with the provisions of Clause 29.
The Agreement will incorporate all agreements between the Employer and the successful Tenderer. It will be kept ready for signature of the successful Tenderer in the office of Employer within 30 days following the notification of award along with the Letter of Acceptance. Within 20 days of receipt, the successful Tenderer will sign the Agreement and deliver it to the Employer.
Upon the furnishing by the successful Tenderer of the Performance Security, the Employer will promptly notify the other Tenderers that their Tenders have been unsuccessful.

29. Security deposit

Within 20 days of receipt of the Letter of Acceptance, the successful Tenderer shall deliver to the Employer a Security deposit in any of the forms given below for an amount equivalent to 5% of the Contract price plus additional security for unbalanced tenders in accordance with Clause 25.5 of ITT and Clause 44 of the Conditions of Contract for all works..:

- Cash or
- Banker's cheque/Demand draft/Pay Order in favor of Managing Director, BSWML payable at Bangalore or
- A bank guarantee in the form given in Section 10; or
- Specified Small Savings Instruments pledged to Managing Director, BSWML payable at Bangalore

If the security deposit is provided by the successful Tenderer in the form of a Bank Guarantee, it shall be issued either by a Nationalized/Scheduled bank.

The security deposit if furnished in cash or demand draft can, if requested, be converted to interest bearing securities at the cost of the successful Tenderer/ contractor.
Failure of the successful Tenderer to comply with the requirements of Sub-Clause 29.1 shall constitute sufficient grounds for cancellation of the award and forfeiture of the Earnest money deposit.

30 Advance Payment and Security:

The Employer will provide an advance payment on the contract price as stipulated in the Conditions of Contract, subject to the maximum amount as stated in the Contract Data.

31. Corrupt or Fraudulent practices

The BSWML requires that the Tenderers/Suppliers/Contractors, observe the highest standard of ethics during the procurement and execution of such contracts. In pursuance of this policy, BSWML :

(a) will reject a proposal for award if it determines that the Tenderer recommended for award has engaged in corrupt or fraudulent practices in competing for the contract in question;

(b) will declare a firm ineligible, either indefinitely or for a stated period of time, to be awarded a BSWML contract if it at any time determines that the firm has engaged in corrupt or fraudulent practices in competing for, or in executing, a BSWML contract.

Furthermore, Tenderers shall be aware of the provision stated in sub-clause 50.2 of the Conditions of Contract.

SECTION 3: QUALIFICATION INFORMATION

The information to be filled in by the Tenderer hereunder will be used for purposes of computing Tender capacity as provided for in Clause 3 of the Instructions to Tenderers. This information will not be incorporated in the Contract.

Constitution or legal status of Tenderer [Attach copy]

Place of Registration _____ (Attach Copy)

Principal place of business: _____

Total value of civil engineering construction works executed and payments received in the last five years (in Rs. Lakhs) Attach Certificate from Chartered Accountant

2019 - 20 ……
2020 - 21 ……
2021 - 22 ……
2022 - 23……
2023 - 24……

Work performed as Prime Contractor (in the same name) on works of similar nature over during the five years specified in 1.2 above.

Project Name	Name of Employer	Descript -tion of Work	Contract Number	Value of Contract Rs. Lakhs	Date of issue of work order	Specified period of completion	Actual date of Actual date of	Remarks explaining reasons for delay in completion of work
1	2	3	4	5	6	7	8	9

Quantities of work executed as prime contractor (in the same name) during the last five years specified in 1.2 above:

Year	Name of Work	Name of Employer	Quantity of work performed (cum)[3]			Remarks (Indicate contract reference)
			Cement Concrete	Masonry	Earthworks	
2019-20						
2020-21						
2021-22						
2022-23						
2023-24						

Information on works for which Tenders have been submitted and works which are yet to be completed as on the date of this Tender.

(A) Existing commitments and on-going works:

Description of Work	Place & State	Contract No. & Date	Name And Address of Employer	Value of Contract (Rs. lakhs)	Stipulated period of completion	Value of works remaining to be completed (Rs. lakhs) Attach Certificates from Engineers –in-Charge	Anticipated date of completion
1	2	3	4	5	6	7	8

(B) Works for which Tenders already submitted:

Description of Work	Place & State	Name and Address of Employer	Estimated value of works (Rs. lakhs)	Stipulated period of completion	Date when decision is expected	Remarks if any
1	2	3	4	5	6	7

1.6. The following items of equipment are considered essential for successfully carrying out the works. The Tenderer should furnish all the information listed below.

Item of Equipment	**Requirement**		
As mentioned above			

Reports on the financial standing of the tenderer, such as profit and loss statements and auditor's reports for the last five years;
Qualification and experience of the key technical and management personnel in permanent employment with the tenderer and those that are proposed to be deployed on this contract, if awarded.

Position	Names	Qualification	Year of Experience (General)	No's required
Project Manager		BE in Civil Engg	3-5 Yrs – in Civil Engineering -Construction projects	3
Site Engineer		BE in Civil Engg	5 Yrs – in BE Civil Engineering -Construction projects	3

1.9. Name, address, and telephone, telex, and fax numbers of the Tenderers' bankers who may provide references if contacted by the Employer. Evidence of access to financial resources to meet the qualification requirement specified in ITT Clause3.3 (b): Cash in hand, Letter of Credit etc. List them below and attach certificate from the Banker in the suggested format as under:

ON BANKS LETTER HEAD

……..

FORMAT OF BANKER'S CERTIFICATE/ LINE OF CREDIT LETTER

(TO BE ISSUED IN THE LETTER HEAD OF THE BANK BRANCH)

Reference Number (Sl. No.)

Place:

Date :

To:

(Name of Address of the Beneficiary)

This is to certified that, Mr./ Mrs. …… (Name of the Customer) having his/ their registered/ Administrative office at ……. Is a customer of our bank and is/ are engaged in …….. (Name of activity). If the said customer is allotted/ awarded with ……. (Brief details of works), we may extend the credit facilities up to Rs. ……. Lakhs to meet his/ their working capital requirement towards the execution of the said work order as per the loan policy of the Bank.

This certificate is valid up to 3 months from the date of issue, i.e. up to dd/mm/yyyy.

Yours faithfully,

Branch Manager.

Proposals for subcontracting components of works amounting to more than 20% of the contract price.

Item of Work	Value of Sub-Contract	Identified Sub-Contractor (Name and address)	Experience of similar work (Attach certificates from the respective Employers.)
1	2	3	4

Information on litigations in which the Tenderer is involved:

Other Party (ies)	Employer	Details of dispute	Amount involved	Remarks showing present status

The proposed methodology and program of construction, backed with equipment planning and deployment, duly supported with broad calculations and quality control procedures proposed to be adopted, justifying their capability of execution and completion of the work as per technical specifications within the stipulated period of completion as per milestones.

SECTION 4: FORMS OF TENDER, LETTER OF ACEPTANCE, NOTICE TO PROCEED WITH THE WORK AND AGREEMENT FORM

Form of Tender

"Village development works in Yeshwanthapura constituency around Seegehalli, Kannahalli & Doddabidrakallu waste processing plants. Village development works in Anekal & Bengaluru South constituency around waste Chikkanagamangala waste processing plant.Village development works in Yeshwanthapura constituency around Subbarayanapalya, Lingadheeranhalli waste processing plants."

To,

Deputy General Manager-2,
BSWML, 1st Floor,UNI
Building, Thimmaiah Road,
Vasanth Nagar, Bangalore-52.

GENTLEMEN,

We offer to execute the Works described above in accordance with the Conditions of Contract accompanying this Tender for the Contract Price of …….. *[in figures]* *(*.....) *[in letters]*.[4]

This Tender and your written acceptance of it shall constitute a binding contract between us. We understand that you are not bound to accept the lowest or any Tender you receive.

The advance payment required is Rs…….

We undertake that, in competing for (and, if the award is made to us, in executing) the above contract, we will strictly observe the laws against fraud and corruption in force in India namely "Prevention of Corruption Act 1988" hereby confirm that this Tender complies with the Tender validity and Earnest money deposit required by the Tenderdocuments.

We attach herewith our current income-tax clearance certificate.

Yours faithfully,

Authorized Signature:
Name & Title of Signatory: _____

Name of Tenderer _____
Address: .....

[4] To be filled in by the Tenderer, together with his particulars and date of submission at the bottom of the Form of Tender

Letter of Acceptance

(letterhead paper of the Employer)

…….[date]

To:

……

……[name and address of the Contractor]

Dear Sirs,

This is to notify you that your Tender dated .....for execution of the "Village development works in Yeshwanthapura constituency around Seegehalli, Kannahalli & Doddabidrakallu waste processing plants.Village development works in Anekal & Bengaluru South constituency around waste Chikkanagamangala waste processing plant.Village development works in Yeshwanthapura constituency around Subbarayanapalya, Lingadheeranhalli waste processing plants."..... for the Contract Price of Rupees……..……..……(…… ……) [amount in words and figures], as corrected and modified in accordance with the Instructions to Tenderers is hereby accepted by our Agency.

You are hereby requested to furnish Security deposit plus additional security for unbalanced tenders in terms of Clause 25.5of ITT, in the form detailed in Clause 29.1 of ITT for an amount of Rs..within 20 days of the receipt of this letter of

Acceptance valid up to 30 days from the date of expiry of Defects Liability Period i.e. up to..... and sign the contract, Failing which action as stated in Para 29.4 of ITT will be taken.

Yours faithfully,

Authorized
Signature Name and
Title of Signatory
Name of Agency

Issue of Notice to proceed with the work

(Letterhead of the Employer)

…….(date)

To

……

……

…… (name and address of the Contractor)

Dear Sirs:

Pursuant to your furnishing the requisite security deposit as stipulated in ITT Clause 29.1 and signing of the contract agreement for the construction of "Village development works in Yeshwanthapura constituency around Seegehalli, Kannahalli & Doddabidrakallu waste processing plants.Village development works in Anekal & Bengaluru South constituency around waste Chikkanagamangala waste processing plant.Village development works in Yeshwanthapura constituency around Subbarayanapalya, Lingadheeranhalli waste processing plants." A Tender Price of Rs…….you are hereby instructed to proceed with the execution of the said works in accordance with the contract documents.

Yours faithfully,

(Signature, name and title of signatory

Authorized to sign on behalf of Employer)

Agreement Form

Agreement

This agreement, made the …….day of ……20..... , between……
…….[name and address of Employer]
(hereinafter called "the Employer") of the one part and …….
……...[name and address of contractor] (hereinafter called "the Contractor") of the other part.

Whereas the Employer is desirous that the Contractor execute ……...
……
……[name and identification number of Contract] (hereinafter called "the Works") and the Employer has accepted the Tender by the Contractor for the execution and completion of such Works and the remedying of any defects therein at a contract price of Rupees'.....

NOW THIS AGREEMENT WITNESSETH as follows:

1. In this Agreement, words and expression shall have the same meanings as are respectively assigned to them in the Conditions of Contract hereinafter referred to, and they shall be deemed to form and be read and construed as part of this Agreement.
2. In consideration of the payments to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the Works and remedy any defects therein in conformity in all aspects with the provisions of the Contract.
3. The Employer hereby covenants to pay the Contractor in consideration of the execution and completion of the Works and the remedying the defects wherein the Contract Price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract.
4. The following documents shall be deemed to form and be read and construed as part of this Agreement, viz:
   - i) Letter of Acceptance;
   - ii) Notice to proceed with the works;
   - iii) Contractor"s Tender;
   - iv) Contract Data;
   - v) Conditions of contract (including Special Conditions of Contract);
   - vi) Specifications;
   - vii) Drawings;
   - viii) Bill of Quantities; and
   - ix) Any other document listed in the Contract Data as forming part of the contract.

In witness whereof the parties thereto have caused this Agreement to be executed the day and year first before written.

The Common Seal of ……
……
was hereunto affixed in the presence of:
Signed, Sealed and Delivered by the said
……
……

in the presence of:
Binding Signature of Employer
……
Binding Signature of Contractor
…….

SECTION 5: CONDITIONS OF CONTRACT

Table of Contents

			Page No.
A.	**General**		
	1. Definitions		25
	2. Interpretation		25
	3. Law governing contract		26
	4. Employers decisions		26
	5. Delegation		26
	6. Communications		26
	7. Subcontracting		26
	8. Other Contractors		26
	9. Personnel		26
	10. Employer's and Contractor's risks	23	
	11. Employer's risks		26
	12 Contractor's risks		27
	13. Insurance		27
	14. Site Investigation Report		27
	15 Query about Contract Data		27
	16 Contractor to construct the Works	24	
	17. The Works to be completed by Intended Completion Date		27
	18 Approvals by the Employer		27
	19. Safety		28
	20. Discoveries		28
	21. Possession of the Site		28
	22. Access to the Site		28
	23. Instructions		28
	24. Procedure for resolution of disputes	25	
B.	**Time Control**		
	25. Program		28
	26. Extension of the Intended Completion Date		28
	27. Delays ordered by the Employer		28
	28. Management meetings		29
C.	**Quality Control**		
	29. Identifying defects		29
	30. Tests		29
	31. Correction of defects		29
	32. Uncorrected defects		29
D.	**Cost Control**		
	33 Bill of Quantities (BOQ)		29
	34 Variations		29
	35. Payment for Variations		29
	36. Submission of bills for payment		29
	37 Payments		29
	38. Compensation events		30
	39. Tax		31
	40 Price Adjustment		31
	41. Liquidated damages		31
	42. Advance Payments		31
	43. Securities		31
	44. Cost of repairs		31
E	**Finishing of Contract**		
	45. Completion		32
	46. Taking Over		32
	47. Final account		32
	48. As built drawings and/or Operating and Maintenance Manuals	29	
	49. Termination		32
	50 Payment upon termination		33
	51. Property		33
	52. Release from performance		33
F	**Special Conditions of Contract**		33

Conditions of Contract

A. General

1. Definitions

Terms which are defined in the Contract Data are not also defined in the Conditions of Contract but keep their defined meanings. Bold letters are used to identify defined terms.
Bill of Quantities means the priced and completed Bill of Quantities forming part of the Tender.
Compensation events are those defined in Clause 38 hereunder.
The **Completion Date** is the date of completion of the Works as certified by the Employer in accordance with Sub Clause 46.1.
The **Contract** is the contract between the Employer and the Contractor to execute, complete and maintain the Works. It consists of the documents listed in Clause 2.2 below.
The **Contract Data** defines the documents and other information which comprise the Contract.
The **Contractor** is a person or corporate body who's Tender to carry out the Works has been accepted by the Employer.
The **Contractor's Tender** is the completed Tender document submitted by the Contractor to the Employer.
The **Contract price** is the price stated in the Letter of Acceptance and thereafter as adjusted in accordance with the provisions of the Contract.
Days are calendar days; **months** are calendar months.
A **Defect** is any part of the Works not completed in accordance with the Contract.
The **Defects liability period** is the period named in the Contract Data and calculated from the Completion Date which is 12 months for this project.
The **Employer** is the party who will employ the Contractor to carry out the Works.
Equipment is the Contractor's machinery and vehicles brought temporarily to the Site to construct the Works.
The **Initial Contract price** is the Contract Price listed in the Employer's Letter of Acceptance.
The **Intended Completion Date** is the date on which it is intended that the Contractor shall complete the Works. The Intended Completion Date is specified in the Contract Data. The Intended Completion Date may be revised onlyby the Employer by issuing an extension of time.
Maintenance Period is the period named in the Contract Data, during which Contractor shall maintain the works completed by him for a period of 12 months effective from last day of Defect Liability Period
Materials are all supplies, including consumables, used by the contractor for incorporation in the Works.
Plant is any integral part of the Works which is to have a mechanical, electrical, electronic or chemical or biological function.
The **Site** is the area defined as such in the Contract Data.
Specification means the Specification of the Works included in the Contract and any modification or addition made or approved by the Employer.
The **Start Date** is given in the Contract Data. It is the date when the Contractor shall commence execution of the works. It does not necessarily coincide with any of the Site Possession Dates.
A **Subcontractor** is a person or corporate body who has a Contract with the Contractor to carry out a part of the work in the Contract which includes work on the Site.
A **Variation** is an instruction given by the Employer which varies the Works.
The **Works** are what the Contract requires the Contractor to construct, install, and turn over to the Employer, as defined in the Contract Data.

2. Interpretation

In interpreting these Conditions of Contract, singular also means plural, male also means female or neuter, and the other way around. Headings have no significance. Words have their normal meaning under the language of the Contract unless specifically defined. The Employer will provide instructions clarifying queries about the Conditions of Contract.
The documents forming the Contract shall be interpreted in the following order of priority:

(1) Agreement
(2) Letter of Acceptance, notice to proceed with the works
(3) Contractor's Tender
(4) Contract Data

(5) Conditions of Contract
(6) Specifications
(7) Drawings
(8) Bill of quantities and
(9) any other document listed in the Contract Data as forming part of the Contract.

3. Law governing contract

The law governing the Contract is the Laws of India supplanted by the Karnataka Local Acts.

4. Employer's decisions

Except where otherwise specifically stated, the Employer will decide contractual matters between the Employer and the Contractor.

5. Delegation

The Employer may delegate any of his duties and responsibilities to other people after notifying the Contractor and may cancel any delegation after notifying the Contractor.

6. Communications

Communications between parties which are referred to in the conditions are effective only when in writing. A notice shall be effective only when it is delivered (in terms of Indian Contract Act).

7. Subcontracting (Deleted)

Deleted.

8. Other Contractors

The Contractor shall cooperate and share the Site with other contractors, public authorities, utilities, and the Employer.

9. Personnel

The Contractor shall employ the technical personnel (of number and qualifications) as may be stipulated by GOK from time to time during the execution of the work. The technical staff so employed shall be available at site as may be stipulated by the Employer.
If the Employer asks the Contractor to remove a person who is a member of the Contractor's staff or his work force stating the reasons, the Contractor shall ensure that the person leaves the Site within seven days and has no further connection with the work in the Contract.

10. Employer's and Contractor's risks

The Employer carries the risks which this Contract states are Employer's risks, and the Contractor carries the risks which this Contract states are Contractor's risks.

11. Employer's risks

The Employer is responsible for the excepted risks which are:
(a) rebellion, riot commotion or disorder unless solely restricted to employees of the Contractor or his Sub-Contractors arising from the conduct of the Works; or
(b) a cause due solely to the design of the Works, other than the Contractor's design; or
(c) any operation of the forces of nature (in so far as it occurs on the Site) which an experienced contractor:
    (i) could not have reasonably foreseen; or
    (ii) could reasonably have foreseen, but against which he could not reasonably have taken at least one of the following measures;

(A) prevent loss or damage to physical property from occurring by taking appropriate measures or
(B) insure against such loss or damage

12. Contractor's risks

All risks of loss of or damage to physical property and of personal injury and death which arise during and in consequence of the performance of the Contract other than the excepted risks are the responsibility of the Contractor.

13. Insurance:

The Contractor shall prior to commencing the works, effect and thereafter maintain insurances , in the joint names of the Employer and the Contractor, (cover from the first working day after the Start Date to the end of Defects Liability Period), in the amounts stated in the Contract Data :

(a) for loss of or damage to the Works, Plants and Materials and the Contractor's equipment;
(b) for liability of both Parties for loss, damage, death and injury to third parties or their property arising out of the Contractor's performance of the Contract including the Contractor's liability for damage to the Employer's property other than the Works and
(c) for liability of both Parties and of any Employer's representative for death and injury to the Contractor's personnel except to the extent that liability arises from the negligence of the Employer, any Employer's representative or their Employees.

Policies and certificates for insurance shall be delivered by the Contractor to the Employer for his approval before the Start Date. All such insurance shall provide for compensation to be payable to rectify the loss or damage incurred. All payments received from insurers relating to loss or damage shall be held jointly by the Parties and usedfor the repair of the loss or damage or as compensation for loss or damage that is not to be repaired.
If the Contractor fails to effect or keep in force any of the insurances referred to in the previous sub-clauses or fails to provide satisfactory evidence, policies or receipts, the Employer may without prejudice to any other right or remedy, effect insurance for the cover relevant to such default and pay the premiums due and recover the same as a deduction from any other monies due to the Contractor. If no payments is due, the payment of the premiums shall bea debt due.
Alterations to the terms of an insurance shall not be made without the approval of the Employer.
Both Parties shall comply with any conditions of the insurance policies.

14. Site Investigation Reports:

The Contractor, in preparing the tender, shall rely on any site investigation reports referred to in the Contract data, supplemented by any information available to the Tenderer.

15. Queries about the Contract Data

The Employer will clarify queries on the Contract Data.

16. Contractor to construct the Works

The Contractor shall construct the Works in accordance with the Specification and Drawings.

17. The Works to be completed by the Intended Completion Date

The Contractor may commence execution of the Works on the Start Date and shall carry out the Works in accordance with the program submitted by the Contractor, as updated with the approval of the Employer, and complete them by the Intended Completion Date.

18. Approval by the Employer:

The Contractor shall submit Specification and drawings showing the proposed Temporary Works to the Employer, who is to approve them if they comply with the Specifications and Drawings.
The Contractor shall be responsible for the design of Temporary Works
The Employer's approval shall not alter the Contractor's responsibility for design of the Temporary Works.

The Contractor shall obtain approval of third parties to the design of third parties to the design of the temporary Works where required.
All Drawings prepared by the Contractor for the execution of the temporary or permanent Works, are subject to prior approval by the Employer before their use.

19. Safety

The Contractor shall be responsible for the safety of all activities on the Site.

20. Discoveries

20..1 Anything of historical or other interest or of significant value unexpectedly discovered on the Site is the property of the Employer. The Contractor is to notify the Employer of such discoveries and carry out the Employer's instructions for dealing with them.

21. Possession of the Site

The Employer shall give possession of all parts of the Site to the Contractor. If possession of a part is not given by the date stated in the Contract Data the Employer is deemed to have delayed the start of the relevant activities and this will be Compensation Event.

22. Access to the Site

The Contractor shall allow the Employer and any person authorized by the Employer access to the Site, to any place where work in connection with the Contract is being carried out or is intended to be carried out and to any place where materials or plant are being manufactured / fabricated / assembled for the works.

23. Instructions

The Contractor shall carry out all instructions of the Employer which comply with the applicable laws where the Site is located.

24. Procedure for resolution of Disputes:

If the Contractor is not satisfied with the decision taken by the Employer, the dispute shall be referred by either party to Arbitration within 30 days of the notification of the Employer's decision.
If neither party refers the dispute to Arbitration within the above 30 days, the Employer's decision will be final and binding.
The Arbitration shall be conducted in accordance with the arbitration procedure stated in the Special Conditions of Contract.

B. Time Control

25. Program

Within the time stated in the Contract Data the Contractor shall submit to the Employer for approval a Program showing the general methods, arrangements, order, and timing for all the activities in the Works.
The Employer's approval of the Program shall not alter the Contractor's obligations. The Contractor may revise the Program and submit it to the Employer again at any time. A revised Program is to show the effect of Variations and Compensation Events.

26. Extension of the Intended Completion Date

The Employer shall extend the Intended Completion Date if a Compensation Event occurs or a Variation is issued which makes it impossible for Completion to be achieved by the Intended Completion Date.
The Employer shall decide whether and by how much to extend the Intended Completion Date within 21 days of the Contractor asking the Employer for a decision upon the effect of a Compensation Event or Variation and submitting full supporting information.

27. Delays ordered by the Employer

The Employer may instruct the Contractor to delay the start or progress of any activity within the Works.

28. Management meetings

The Employer may require the Contractor to attend a management meeting. The business of a management meeting shall be to review the progress achieved and the plans for remaining work.
The responsibility of the parties for actions to be taken is to be decided by the Employer either at the management meeting or after the management meeting and stated in writing to be distributed to all who attended the meeting.

C. Quality Control

29. Identifying defects

The Employer shall check the Contractor's work and notify the Contractor of any Defects that are found. Such checking shall not affect the Contractor's responsibilities. The Employer may instruct the Contractor to search for a Defect and to uncover and test any work that the Employer considers may have a Defect

30. Tests

If the Employer instructs the Contractor to carry out a test not specified in the Specification to check whether any work has a Defect and the test shows that it does, the Contractor shall pay for the test and any samples. If there is no Defect the test shall be a Compensation Event.

31. Correction of defects

The Employer shall give notice to the Contractor of any Defects before the end of the Defects Liability Period, which begins at Completion and is defined in the Contract Data. The Defects Liability Period shall be extended for as long as Defects remain to be corrected.
Every time notice of a Defect is given, the Contractor shall correct the notified Defect within the length of time specified by the Employer's notice.

32. Uncorrected defects

If the Contractor has not corrected a Defect within the time specified in the Employer's notice, the Employer will assess the cost of having the Defect corrected, and the Contractor will pay this amount.

D. Cost Control

33. Bill of Quantities (BOQ)

The BOQ shall contain items for the construction, installation, testing, and commissioning work to be done by the Contractor.
The BOQ is used to calculate the Contract Price. The Contractor is paid for the quantity of the work done at the rate in the BOQ for each item

34. Variations

The Employer shall have power to order the Contractor to do any or all of the following as considered necessary or advisable during the progress of the work by him

(a) Increase or decrease of any item of work included in the Bill of Quantities (BOQ);
(b) Omit any item of work;
(c) Change the character or quality or kind of any item of work;
(d) Change the levels, lines, positions and dimensions of any part of the work;
(e) Execute additional items of work of any kind necessary for the completion of the works; and
(f) Change in any specified sequence, methods or timing of construction of any part of the work.

The Contractor shall be bound to carry out the work in accordance with any instructions in this connection, which may be given to him in writing by the Employer and such alteration shall not vitiate or invalidate the contract.

Variations shall not be made by the Contractor without an order in writing by the Employer, provided that no order in writing shall be required for increase or decrease in the quantity of an item appearing in the BOQ so long as the work executed conforms to the approved drawings.
The Contractor shall promptly request in writing to the Employer to confirm verbal orders and the officer issuing oral instructions shall confirm it in writing within 30 days, failing which the work shall be carried out as though there is no variation. In case variation is approved it shall be accompanied by BOQ, failing which the contractor shall be responsible for deviation if any. Further, approval of Govt. / BSWML has to be obtained for the variation exceeding 5%.

35. Payments for Variations

Payment for increase in the quantities of an item in the BOQ up to 25% of that provided in the Bill of Quantities shall be made at the rates quoted by the Contractor.
For quantities in excess of 125% of the tendered quantity of an item as given in the BOQ, the Contractor shall be paid at the rate entered in or derived from in the Schedule of Rates (applicable for the area of the work and current atthe time of award of contract) plus or minus the overall percentage of the original tendered rates over the current Schedule of Rates prevalent at the time of award of contract.
If there is no rate for the additional, substituted or altered item of the work in the BOQ, efforts would be made to derive the rates from those given in the BOQ or the Schedule of Rates (applicable for the area of the work and current at the time of award of contract) and if found feasible the payment would be made at the derived rate for the item plus or minus the overall percentage of the original tendered rates over the current Schedule of Rates prevalent at the time of award of contract
If the rates for additional, substituted or altered item of work cannot be determined either as at 35.1 or 35.2 or 35.3 above, the Contractor shall be requested to submit his quotation for the items supported by analysis of the rate or rates claimed, within 7 days.
If the Contractor's quotation is determined unreasonable, the Employer may order the Variation and make a change to the Contract Price which shall be based on Employer's own forecast of the effects of the Variation on the Contractor's costs.
If the Employer decides that the urgency of varying the work would prevent a quotation being given and considered without delaying the work, no quotation shall be given and the Variation shall be treated as a Compensation Event.
Under no circumstances the Contractor shall suspend the work on the plea of non-settlement of rates for items falling under this Clause.

36. Submission of bills for payment

The Contractor shall submit to the Employer monthly bills of the value of the work completed less the cumulative amount paid previously.
The Employer shall check the Contractor's bill and determine the value of the work executed which shall comprise of (i) value of the quantities of the items in the BOQ completed and (ii) valuation of Variations and Compensation Events.
The Employer may exclude any item paid in a previous bill or reduce the proportion of any item previously paid in the light of later information.

37. Payments

Payments shall be adjusted for deductions for advance payments other than recoveries in terms of contract and taxes, at source, as applicable under the law. The Employer shall pay the Contractor the within 60 days of submission of bill. The contractor shall be liable to pay liquidated damages for shortfall in progress. For progress beyond theagreed programmer payment is subject to availability of the grants.
Items of the Works for which no rate or price has been entered in will not be paid for by the Employer and shall be deemed covered by other rates and prices in the Contract.

38. Compensation events

The following are Compensation events unless they are caused by the Contractor:

(a) The Employer does not give access to a part of the Site by the Site Possession Date stated in the Contract Data.
(b) The Employer orders a delay or does not issue drawings, specifications or instructions required for execution of works on time.

(c) The Employer instructs the Contractor to uncover or to carry out additional tests upon work which is then found to have no Defects.
(d) The Employer gives an instruction for dealing with an unforeseen condition, caused by the Employer, or additional work required for safety or other reasons.
(e) The effect on the Contractor of any of the Employer's Risks.
(f) The Employer unreasonably delays issuing a Certificate of Completion.
(g) Other Compensation Events listed in the Contract Data or mentioned in the Contract.

If a Compensation Event would cause additional cost or would prevent the work being completed before the Intended Completion Date, the Contract Price shall be increased and/or the Intended Completion Date is extended. The Employer shall decide whether and by how much the Contract Price shall be increased and whether and by how much the Intended Completion Date shall be extended.
As soon as information demonstrating the effect of each Compensation event upon the Contractor's forecast cost has been provided by the Contractor, it is to be assessed by the Employer and the Contract Price shall be adjusted accordingly. If the Contractor's forecast is deemed unreasonable, the Employer shall adjust the Contract Price based on Employer's own forecast. The Employer will assume that the Contractor will react competently and promptly to the event.
The Contractor shall not be entitled to compensation to the extent that the Employer's interests are adversely affected by the Contractor not having given early warning or not having cooperated with the Employer.

39. Tax

The rates quoted by the Contractor shall be deemed to be exclusive of GST and inclusive of other taxes that the Contractor will have to pay for the performance of this Contract. The Employer will perform such duties in regard to the deduction of such taxes at source as per applicable law.

40. Price Adjustment: Refer Section 6: Contract Data

41. Liquidated damages:

The Contractor shall pay liquidated damages to the Employer at the rate per day stated in the Contract Data for each day that the Completion Date is later than the Intended Completion Date (for the whole of the works or the milestone as stated in the Contract Data). The total amount of liquidated damages shall not exceed the amount defined in the Contract Data. The Employer may deduct liquidated damages from payments due to the Contractor. Payment of liquidated damages does not affect the Contractor's liabilities.
If the Intended Completion Date is extended after liquidated damages have been paid, the Employer shall correct any overpayment of liquidated damages by the Contractor by adjusting the next payment of bill.

42. Advance Payments: Refer Section 6: Contract Data

43. Securities:

The Security deposit (including additional security for unbalanced tenders) shall be provided to the Employer no later than the date specified in the Letter of Acceptance and shall be issued in an amount and form and type of instrument acceptable to the Employer. The Security deposit shall be valid until a date 30 days from the date of expiry of Defects Liability Period and the additional security for unbalanced tenders shall be valid until a date 30 days from the date of issue of the certificate of completion.

44. Cost of Repairs:

Loss or damage to the Works or Materials to be incorporated in the Works between the Start Date and the end of the Defects Correction periods shall be remedied by the Contractor at the Contractor's cost if the loss or damage arises from the Contractor's acts or omissions.

E. Finishing the Contract

45. Completion

The Contractor shall request the Employer to issue a Certificate of Completion of the Works and the Employer will do so upon deciding that the Work is completed.

46. Taking over

The Employer shall take over the Site and the Works within seven days of issuing a certificate of Completion.

47. Final account

The Contractor shall supply to the Employer a detailed account of the total amount that the Contractor considers payable under the Contract before the end of the Defects Liability Period. The Employer shall issue a Defect Liability Certificate and certify any final payment that is due to the Contractor within 90 days of receiving the Contractor's account if it is correct and complete. If it is not, the Employer shall issue within 90 days a schedule that states the scope of the corrections or additions that are necessary. If the Final Account is still unsatisfactory after it has been resubmitted, the Employer shall decide on the amount payable to the Contractor and make payment within 60 days of receiving the Contractor's revised account.

48. As built drawings and /or Operating and Maintenance Manuals

If "as built" (*Completion drawings*) Drawings and/or operating and maintenance manuals are required, the Contractor shall supply them by the dates stated in the Contract Data.
If the Contractor does not supply the Drawings by the dates stated in the Contract Data, or they do not receive the Employer's approval, the Employer shall withhold the amount stated in the Contract Data from payments due to the Contractor.

49. Termination

The Employer may terminate the Contract if the other party causes a fundamental breach of the Contract.
Fundamental breaches of Contract include, but shall not be limited to the following:

(a) the Contractor stops work for 45 days when no stoppage of work is shown on the current Program and the stoppage has not been authorized by the Employer;
(b) Deleted.
(c) The Contractor becomes bankrupt or goes into liquidation other than for a reconstruction or amalgamation;
(d) Deleted.
(e) the Employer gives Notice that failure to correct a particular Defect is a fundamental breach of Contract and the Contractor fails to correct it within a reasonable period of time determined by the Employer;
(f) the Contractor does not maintain a security which is required;
(g) the Contractor has delayed the completion of works by the number of days for which the maximum number of liquidated damages can be paid as defined in the Contract data; and
(h) if the Contractor, in the judgment of the Employer has engaged in corrupt or fraudulent practices in competing for or in the executing the Contract.
For the purpose of this paragraph: "corrupt practice" means the offering, giving, receiving or soliciting of anything of value to influence the action of a public official in the procurement process or in contract

execution. “Fraudulent practice” means a misrepresentation of facts in order to influence a procurement process or the execution of a contract to the detriment of the Borrower, and includes collusive practice among Tenderers (prior to or after Tender submission) designed to establish Tender prices at artificial non-competitive levels and to deprive the Borrower of the benefits of free and open competition.”
When either party to the Contract gives notice of a breach of contract to the Employer for a cause other than those listed under Sub Clause 49.2 above, the Employer shall decide whether the breach is fundamental or not.
Notwithstanding the above, the Employer may terminate the Contract for convenience.
If the Contract is terminated the Contractor shall stop work immediately, make the Site safe and secure and leave the Site as soon as reasonably possible.

50. Payment upon Termination

If the Contract is terminated because of a fundamental breach of Contract by the Contractor, the Employer shall prepare bill for the value of the work done less advance payments received up to the date of the bill, less other recoveries due in terms of the contract, less taxes due to be deducted at source as per applicable law and less the percentage to apply to the work not completed as indicated in the Contract Data. Additional Liquidated Damages shall not apply. If the total amount due to the Employer exceeds any payment due to the Contractor the difference shall be a debt payable to the Employer.
If the Contract is terminated at the Employer's convenience or because of a fundamental breach of Contract by the Employer, the Employer shall prepare bill for the value of the work done, the reasonable cost of removal of Equipment, repatriation of the Contractor's personnel employed solely on the Works, and the Contractor's costs of protecting and securing the Works and less advance payments received up to the date of the certificate, less other recoveries due in terms of the contract, and less taxes due to be deducted at source as per applicable law and make payment accordingly.

51. Property

All materials on the Site, Plant, Equipment, Temporary Works and Works are deemed to be the property of the Employer, if the Contract is terminated because of a Contractor’s default.

52. Release from performance

If the Contract is frustrated by any event entirely outside the control of either the Employer or the Contractor the Employer shall certify that the Contract has been frustrated. The Contractor shall make the Site safe and stop work as quickly as possible after receiving this certificate and shall be paid for all work carried out before receiving it and for any work carried out afterwards to which commitment was made

F. Special Conditions of Contract

1. Labour :

The Contractor shall, unless otherwise provided in the Contract, make his own arrangements for the engagement of all staff and labour, local or other, and for their payment, housing, feeding and transport.

The Contractor shall, if required by the Employer, deliver to the Employer a return in detail, in such form and at such intervals as the Employer may prescribe, showing the staff and the numbers of the several classes of labour from time to time employed by the Contractor on the Site and such other information as the Employer may require.

2. Compliance with labour regulations:

During continuance of the contract, the Contractor shall abide at all times by all existing labour enactments and rules made there under, regulations, notifications and bye laws of the State or Central Government or local authority and any other labour law (including rules), regulations, bye laws that may be passed or notification that may be issued under any labour law in future either by the State or the Central Government or the local authority. The Contractor shall keep the Employer indemnified in case any action is taken against the Employer by the competent authority on account of contravention of any of the provisions of any Act or rules made there under, regulations or notifications including amendments. If the Employer is caused to pay or reimburse, such amounts as may be necessary to cause or observe, or for non-observance of the provisions stipulated in the notifications/bye laws/Acts/Rules/regulations including amendments, if any, on the part of the Contractor, Employer shall have the right to deduct any money due

to the Contractor including his amount of security deposit. The Employer shall also have right to recover from the Contractor any sum required or estimated to be required for making good the loss or damage suffered by the Employer.

The employees of the Contractor in no case shall be treated as the employees of the Employer at any point of time.

3. Protection of Environment:

The contractor shall take all reasonable steps to protect the environment on and off the Site and to avoid damage or nuisance to persons or to property of the public or others resulting from pollution, noise or other causes arising as a consequence of his methods of operation. During continuance of the contract, the contractor shall abide at all times by all existing enactments on environmental protection and rules made there under, regulations, notifications and bye-laws of the State or Central Government, or local authorities and any other law, bye-law, regulations that maybe passed or notification that may be issued in this respect in future by the State or Central Government or the local authority.

4. Arbitration (Clause 24):

4.1 The procedure for arbitration shall be as follows:

(a) In case of dispute or difference arising between the Employer and the Contractor relating to any matter arising out of or connected with this agreement it shall be settled in accordance with the Arbitration and Conciliation Act 1996. The disputes or differences shall be referred to a Sole Arbitrator. The Sole Arbitrator shall be appointed by agreement between the parties; failing such agreement, by the Appointing Authority (any one of the Organizations as per list enclosed in Annexure).

(b) Arbitration proceedings shall be held at Bangalore, Karnataka, India

(c) The cost and expenses of arbitration proceedings will be paid as determined by the Arbitrator. However the expenses incurred by each party in connection with the preparation, presentation, etc., shall be borne by each party itself.

(d) Performance under the contract shall continue during the arbitration proceedings and payments due the Contractor by the Employer shall not be withheld, unless they are the subject matter of the arbitration proceedings.

5. In the case of the death of a Contractor after executing the agreement / commencement of the work, his legal heir, if an eligible registered Contractor and willing can execute and complete the work at the accepted tender rates irrespective of the cost of the work.

6. The Contractor shall provide One four-wheeler along with driver, fuel expenses to Project Engineers in-charge of work to facilitate and co-ordinate the supervision of the work.

7. The Contractor shall establish field lab and field office to facilitate quality assurance of execution of works.

Annexure:

LIST OF ORGANIZATIONS WHO ARE CONSIDERED AS APPOINTING AUTHORITY FOR APPOINTMENT OF ARBITRATORS

1. Indian Council of Arbitration, New Delhi;
2. International Centre for Alternative Disputes Resolution (India);
3. Indian Roads Congress;
4. Indian Building Congress;
5. Indian Institute of Bridge Engineers;
6. Indian Institute of Public Health Engineers;
7. Institute of Water Works

SECTION 6: CONTRACT DATA

Items marked "N/A" do not apply in this Contract.

The following documents are also part of the Contract:	**Clause Reference**
• The Schedule of Operations Manuals	[48]
• The Methodology and Program of Construction	[25]
• Site Investigation Reports	[14]
• The Schedule of Key and Critical Equipment to be deployed on the work as per agreed program of construction.	[25]

The Employer is:

Name: **The Managing Director** [1.1]
BSWML, Bangalore

Name of authorized Representative:
Office of the Deputy General Manager-2,
BSWML,1st Floor, UNI Building,
Thimmaiah road, Bengaluru-560052

The name and identification number of the Contract is **DGM-2/BSWML/TEND/04/2024-25, Date:09.09.2024**
[1.1]

"Village development works in Yeshwanthapura constituency around Seegehalli, Kannahalli & Doddabidrakallu waste processing plants.Village development works in Anekal & Bengaluru South constituency around waste Chikkanagamangala waste processing plant.Village development works in Yeshwanthapura constituency around Subbarayanapalya, Lingadheeranhalli waste processing plants."

The Works consist of Construction of new roads, drains and providing other basic infrastructure works.
The start date shall be the date of issue of notice to proceed with the work. [1.1]

The Intended Completion Date for the whole
of the Works is **12 months** with the following milestones [17, 26]

The Defects Liability Period: 12 Months for Village developmental works.

The Site Possession Date is: Date of work order [21]

The Site is located at **Yeshwanthapura, Anekal & Bangalore South constituency** [1.1]

"Village development works in Yeshwanthapura constituency around Seegehalli, Kannahalli & Doddabidrakallu waste processing plants.Village development works in Anekal & Bengaluru South constituency around waste Chikkanagamangala waste processing plant.Village development works in Yeshwanthapura constituency around Subbarayanapalya, Lingadheeranhalli waste processing plants."

Insurance requirements are as under:

	Type of Cover	Minimum cover for Insurance[6]
(i)	Works and of Plant and materials	The sum stated in the Agreement (contract Value) plus 20%
(ii)	Loss or damage to equipment	Full replacement cost
(iii)	Loss or damage to property of Third Party	Full replacement cost
(iv)	Personal injury or death insurance (a) for Third Party[7]	5.00 Lakhs each person
	(b) for Contractor's employees or labour	In accordance with the statutory requirements applicable to Karnataka Rs. 5.00Lakhs each person

Price Adjustment Formula
R= Value of work as defined in Clause 40.1 of Conditions of Contract.
Adjustment for labour component:

(i) Price adjustment for increase or decrease in the cost due to labour shall be paid in accordance with the following formula:

VL = 0.85 X PL /100 X R X(Li - Lo) /Lo Where,

VL = Increase or decrease in the cost of work during the quarter under consideration due to changes in rates for local labour;

Lo = The average consumer price index for industrial workers for ……. Centre for the quarter preceding the date of opening of tenders as published by the Labour Bureau, Ministry of Labour, Government of India;

Li = The average consumer price index for industrial workers for ……. Centre for the quarter under consideration as published by Labour Bureau, Ministry of Labour, Government of India

PL = Percentage of labour component of the work

Adjustment for Cement Component:

(ii) Price adjustment for increase or decrease in the cost of cement component procured by the contractor shall be paid in accordance with the following formula.

VC = 0.85 X PC /100 X R X (Ci - Co) /Co , Where,

VC = Increase or decrease in the cost of the work during the quarter under consideration due to changes in the rates for cement;

Co = The all India average wholesale price index for cement (Ordinary Portland Cement) for the quarter preceding the date of opening of the tenders as published by the Office of Economic Advisor, Ministry of Commerce and Industry, Government of India , New Delhi;

Ci = The all India average wholesale price index for cement (Ordinary Portland Cement) for the quarter under consideration as published by the Office of Economic Advisor, Ministry of Commerce and Industry, Government of India, New Delhi

PC = Percentage of cement component of the work

Note: For the application of this clause index of Ordinary Portland Cement has been chosen to represent Cement Group

Adjustment for steel component:

(iii) Price adjustment for increase or decrease in the cost of steel procured by the contractor shall be paid in accordance with the following formula.

VS = 0.85 X PS /100 X R X (Si – So)/So where,

VS = Increase or decrease in the cost of work during the quarter under consideration due to changes in the rates for steel;

So = The all India average wholesale price index for steel (M.S.Bars and rods) for the quarter preceding the date of opening of Bids as published by the Office of Economic Advisor, Ministry of Commerce and Industry, Government of India, New Delhi

Si = The all India average wholesale price index for steel (M.S. Bars and Rods) for the quarter under consideration as published by the Office of Economic Advisor, Ministry of Commerce and Industry, New Delhi

PS = Percentage of steel component of the work

Note: For the application of this clause, index of M.S.Bars and Rods has been chosen to represent steel group.

Adjustment of Bitumen Component:

(iv) Price adjustment for increase or decrease in the cost of bitumen shall be paid in accordance with the following formula:

VB = 0.85 X PB/100 X R X (Bi – Bo)/Bo , Where

VB = Increase or decrease in the cost of work during the quarter under consideration due to changes in the rate for bitumen.

Bo = The official retail price of bitumen at the IOC /HPCL/BPL or any other depot at ……. on the day 30 days prior to the date of opening of Bids.

Bi = The official retail price of bitumen at the IOC/HPCL/BPL or any other depot at ……. for the 15th day of the middle calendar month of the quarter under consideration.

PB = Percentage of bitumen component of the work.

Adjustment of Fuel and Lubricant component:

(v) Price adjustment for increase or decrease in cost of Fuel and Lubricants shall be paid in accordance with the

following formula:

VF = 0.85 X PF /100 X R X (Fi - Fo)/ Fo, Where,

VF = Increase or decrease in the cost of work during the quarter under consideration due to changes in the rates for Fuel and Lubricants.

Fo = The official retail price of High Speed Diesel (HSD) at the IOC/HPCL/BPL or other consumer pump at ……. on the day 30 days prior to the date of opening of Bids.

Fi = The official retail price of HSD at the IOC/HPCL/BPL or other consumer pump at ……. for the 15th day of the middle calendar month of the quarter under consideration.

PF = Percentage of Fuel and Lubricant component of the work.

Note: For the application of this Clause the price of HSD has been chosen to represent Fuel and Lubricant Group

Adjustment for Plant and Machinery Spares Component:

(vi) Price adjustment for increase or decrease in the cost of plant and machinery spares procured by the contractor shall be paid in accordance with the following formula:

VP = 0.85 X PP/100 X R X (Pi – Po)/Po , Where

VP = Increase or decrease in the cost of work during the quarter under consideration due to changes in the rates for plant and machinery spares.

Po = The all India average wholesale price index for Heavy machinery and parts for the quarter preceding the date of opening of bids, as published by the Office of the Economic Advisor, Ministry of Commerce and Industry, Government of India, New Delhi

Pi = The all India average wholesale price index for Heavy machinery and parts for the quarter under consideration as published by the Office of the Economic Advisor, Ministry of Commerce and Industry, Government of India, New Delhi

PB = Percentage of Plant and Machinery Spares component of the work.

Note: For the application of this Clause index of Heavy Machinery and Parts has been chosen to represent the Plant and Machinery Spares Group.

Adjustment for Other materials.

(vii) Price adjustment for increase or decrease in the cost of other materials other than cement, steel, bitumen and Fuel and Lubricants48, procured by the contractor shall be paid in accordance with the following formula:

VM = 0.85 X PM/100 X R X (Mi – Mo)/Mo , Where

VM = Increase or decrease in the cost of work during the quarter under consideration due to changes in the rates for local materials other than cement, steel, bitumen and Fuel and Lubricants.

Mo = The all India average wholesale price index for all commodities for the quarter preceding the date of opening of bids, as published by the Office of the Economic Advisor, Ministry of Commerce and Industry, Government of India, New Delhi

Mi = The all India average wholesale price index for all commodities for the quarter under consideration as published

by the Office of the Economic Advisor, Ministry of Commerce and Industry, Government of India, New Delhi

PM = Percentage of other material component (Other than cement, steel, bitumen and Fuel and Lubricants) of the work.

The following percentages will govern the price adjustment for the entire contract:

1. Labour – PL …….. %

2. Cement – PC ……%

3. Steel – PS ……%

4. Bitumen – PB ……%

5. Fuel and Lubricants – PF ……%

6 Plant and Machinery Spares – PP …….%

7 Other materials – PM …….%

TOTAL 100 %

The liquidated damages for the whole of the works are Rs.5,95,600.00 (amount) per day and that for the Milestones are as under:

For Milestone 1:	Rs. 1,98,534.00 per day
For Milestone 2:	Rs. 1,98,533.00 per day
For Milestone 3:	Rs. 1,98,533.00 Per day

The maximum amount of liquidated damages for the whole of the works is Ten percent of final contract price. [41]

The amounts of the advance payment are [42]

Nature of Advance	Amount (Rs.)	Conditions to be fulfilled
1. Mobilization	5% of the Contract price	On submission of un-conditional Bank Guarantee. (to be drawn before end of 20% of Contract period)

(The advance payment will be paid to the Contractor no later than 30 days after fulfillment of the above conditions).

Repayment of advance payment for mobilization : [42]

The advance loan shall be repaid with percentage deductions from the interim payments certified by the Engineer under the Contract. Deductions shall commence in the next Interim Payment Certificate following that in which the total of all such payments to the Contractor has reached not less than 15 percent of the Contract Price or Three months from the date of payment of first installment of advance, whichever period concludes earlier, and shall be made at the rate of 7.5% percent of the amounts of all Interim Payment Certificates until such time as the loan has been repaid, always provided that the loan shall be completely repaid prior to the expiry of the original time for completion pursuant to Clauses 17 and 26.

SECTION 8: DRAWINGS

As per approved DPR

BILL OF QUANTITIES

DRAFT TENDER SCHEDULE (DTS)					
SI No	**Description of Item**	**Unit**	**Total Quantity**	**Rate in Rs.**	
				In Figures	**In Words**
1	Removing and refixlng cover slabs of drains and pointing in C.M (1:2)	Sqm	1081.50	121.00	Rupees One Hundred Twenty One Only
2	Earth work excavation by manual means for drains, canals, waste weir draft, approach channels, key trench, foundation of Buildings & Bridges and such similar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work In all kinds of soils Depth upto 1.5 m	Cum	4884.60	266.20	Rupees Two Hundred Sixty Six And Paise Twenty Only
3	Providing and laying in position Cement Concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing, and all the other appurtenances required to complete the work as per technical specifications.2.1.3 Mix 1:3:6 Using 40 mm nominal size graded crushed coarse aggregates	Cum	1004.40	6587.90	Rupees Six Thousand Five Hundred Eighty Seven And Paise Ninety Only

4	Supplying, fitting and placing TMT FE 550 / 550D Steel Reinforcement including cost of all materials, machinery, labour, cleaning, straightening, cutting, bending, hooking, laping/welding joints, tying with binding wire / soft annealed steel wire and other ancilary operations complete as per drawing and technical specification.H. All other type of structures	Tonnes	143.64	86912.10	Rupees Eighty Six Thousand Nine Hundred Twelve And Paise Ten Only
5	Providing and laying in position Cement Concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications.M20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	Cum	2052.00	9168.35	Rupees Nine Thousand One Hundred Sixty Eight And Paise Thirty Five Only
6	Providing and laying 100mm thick pre-cast cover slabs over Road side drains / utility ducts / Rain water harvesting pit of width not exceeding 1000 mm using M20 concrete reinforced with TMT bars Fe 550 @ 6kg/m2, slabs jointed in CM 1:3 proportion and nicely finished Including providing holes in the Cover slabs wherever necessary for easy drainage of surface water including of labour, materials, scaffolding, usage of machinery, curing, lead and lift charges etc, Complete	Sqm	5215.50	1287.00	Rupees One Thousand Two Hundred Eighty Seven Only
7	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead (ii) By Mechanical Means b Prestressed / RCC grade M-20 & Above	Cum	895.68	1218.80	Rupees One Thousand Two Hundred Eighteen And Paise Eighty Only

8	Earth work in surface excavation by mechanical means for lowering & leveling the ground for all works other than foundation in all kinds of soils & upto depth not exceeding 300mm as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenances required to complete the work.In all kinds of soils upto 300 mm depth	Cum	36896.52	104.50	Rupees One Hundred Four And Paise Fifty Only
9	Construction of Granular Sub-Base of required grading as per design mixing in a mechanical mix plant at OMC, carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per clause 401 (v) For Grading -V Material	Cum	15845.74	2735.70	Rupees Two Thousand Seven Hundred Thirty Five And Paise Seventy Only
10	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver/grader in sub-base / base course on well prepared surface and compacting withvibratory roller to achieve the desired density.	Cum	19036.05	2814.90	Rupees Two Thousand Eight Hundred Fourteen And Paise Ninety Only
11	Prime Coat over WMM/WBM Providing and applying primer coat with SS1 grade Bitumen Emulsion on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70 kg/m2 using mechanical means.	Sqm	96414.25	45.10	Rupees Forty Five And Paise Ten Only
12	Providing and laying Dense Graded Bituminous Macadam with 40/60 TPH capacity hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder VG-30, @4.0 per cent by weight of total mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 505 complete in all respects Dense Graded Bituminous Macadam Grading - I for traffic<20	Cum	5357.91	9656.90	Rupees Nine Thousand Six Hundred Fifty Six And Paise Ninety Only

13	Tack coat on Bituminous surface Providing and applying tack coat with RS1 Bituminous Emulsion using emulsion pressure distributor at the rate of 0.20 kg/m2 on the prepared bituminous surface cleaned with mechanical broom	Sqm	107158.25	13.20	Rupees Thirteen And Paise Twenty Only
14	Providing and laying Bituminous Concrete with not less than 40/60 TPH capacity HMP using crushed aggregates of specified grading, premixed with bituminous binder VG-30 @ 4.78% Bitumen and waste plastic 8% of Bitumen of mix and filler,transporting the hot mix to work site, laying with mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No.507 complete in all respects A Bituminous Concrete Grading I Using waste plastic	Cum	4286.33	11100.10	Rupees Eleven Thousand One Hundred And Paise Ten Only
15	Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Bituminous Surface Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 g/m2 area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35:2015.The finished surface to be level,uniform and free from streaks and holes.	Sqm	3845.90	583.00	Rupees Five Hundred Eighty Three Only
16	Construction of dry lean cement concrete Sub- base over a prepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 14:1, aggregate gradation after blending to be as per table 600-1, cement content not to be less than 140 kg/ m3 , optimum moisture content to be determined during trial length construction, concrete strength not to be less than 7 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver with electronic sensor, compacting with 8-10 t vibratory roller, finishing and curing.	Cum	1045.80	5412.00	Rupees Five Thousand Four Hundred Twelve Only

17	Construction of M30 Grade un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with OPC @ 270 kg/m3 and GGBS@ 90 kg/m3, coarse and fine aggregate conforming to IS 383:2016, maximum size of coarse aggregate not exceeding 25 mm, mixed in a batching and mixing plant as per approved mix design transported to site, laid with a paver finisher, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation Pavement Quality M30 grade Concrete (RMC) with OPC & GGBS laid using Paver membrane, sealant primer, joint sealant, debonding strip, dowel bar, tie rod, admixtures, curing compound, steel channels, finishing to lines and grades as per drawing.	Cum	1568.70	8622.90	Rupees Eight Thousand Six Hundred Twenty Two And Paise Ninety Only
18	Loading and Unloading of Stone Boulder/Stone aggregates/Sand/Kankar/Moorum.(Tipper 14 m3)	Cum	42676.80	94.60	Rupees Ninety Four And Paise Sixty Only
19	Cost of Haulage Excluding Loading and Unloading Case-1 : Surfaced Road Taking output 25 tonnes load and lead 10 km = 250 t.km	t.km	554798.41	7.70	Rupees Seven And Paise Seventy Only
20	Supplying of premisc/,nuan/Biomass etc., chemical forspraying to control fly menace with all applicable taxes including all lead and lift charges as per the direction of engineer incharges	Ltr	3150.00	3456.00	Rupees Three Thousand Four Hundred Fifty Six Only
21	Supplying of Sugar to mix with the chcmical along with the water. For spraying to controle fly menace and all applicable taxes including all lead and lift charges as per the direction of engineer incharges	kgs	29400.00	54.00	Rupees Fifty Four Only
22	Spraying of premise chemical solution prepared by mixing the Chemical with sugar and water @ the ratio 5ml of chemical for 1 litre of water to control fly menace. Spraying Labours - 3 Nos	Nos	1890.00	594.00	Rupees Five Hundred Ninety Four Only
23	Supplying preparation and spraying of lemon grass to reduce foul labors and controlin pets including cost of materials and labours for preparation spraying supervision HOM on water tanker fuel charges and crew charges loading unloading transportation labours charges incindenal charges etc... complete and with all lead and lift loading and unloding as per the direction of engineer in charge of work	Ltr	2688000.00	16.20	Rupees Sixteen And Paise Twenty Only

24	Providing Bio product solutions prepared at site and spraying on existing and fresh garbage ,accumulated leachate and surrounding area with effective proportion diluted in water to reduce foul smell and control pests including cost of all materials,labour, HOM on machiney ,loading ,unloading,transportation all lead and lifts, taxes etc., Complete asper specifications and directions of Engineer incharge of work. (Approved Data Rate)	Ltr	3087000.00	29.20	Rupees Twenty Nine And Paise Twenty Only
25	Procuring of spraying machines to spray above solutions including all lead and fil1 charges as per the direction of engineer incharge	Nos	54.00	2430.00	Rupees Two Thousand Four Hundred Thirty Only
26	Supplying ol pyetrum / king fog ctc..,(contains detamethrine 1.25%l by thermal fogging to control mosquito & menace including all lead and lift charges as per the direction of engineer incharges	set	3360.00	3996.00	Rupees Three Thousand Nine Hundred Ninety Six Only
27	Supply mixing of diesel with chemical in required ratio with diesel and petrol in the fogging machine -10 litre/day including all lead and lift charges as per the direction of engineer incharge	Ltr	28350.00	97.20	Rupees Ninety Seven And Paise Twenty Only
28	Labour for fogging in the quarry site and surrounding villages on the vehicle including fogging equipment charges vehicle hire charges and othcr incidental charges with all lead and lifts.	nos	6300.00	594.00	Rupees Five Hundred Ninety Four Only
29	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, including removal and disposal of top organic soil not exceeding 150 mm in thickness. b In area of thorny jungle	100 m^2	70.37	1545.00	Rupees One Thousand Five Hundred Forty Five Only
30	Earth work excavation by manual means for drains, canals, waste weir draft, approach channels, key trench, foundation of Buildings & Bridges and such similar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour,	Cum	1988.07	249.26	Rupees Two Hundred Forty Nine And Paise Twenty Six Only

	tools & other appurtenaces required to complete the work In all kinds of soils Depth upto 1.5 m				
31	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed raded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:3:6 Using 40 mm nominal size graded crushed coarse aggregates	Cum	61.65	6168.67	Rupees Six Thousand One Hundred Sixty Eight And Paise Sixty Seven Only
32	Providing and laying in position Cement Concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) M20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	Cum	102.00	8792.13	Rupees Eight Thousand Seven Hundred Ninety Two And Paise Thirteen Only
33	FabricationSupplying, fitting and placing TMT FE 550 / 550D Steel Reinforcement including cost of all materials, machinery, labour, cleaning, straightening, cutting, bending, hooking, laping/welding joints, tying with binding wire / soft annealed steel wire and other ancilary operations complete as per drawing and technical specification-All other type of structures	Tonnes	6.97	81381.33	Rupees Eighty One Thousand Three Hundred Eighty One And Paise Thirty Three Only

34	Providing and laying 100mm thick pre-cast cover slabs over Road side drains / utility ducts / Rain water harvesting pit of width not exceeding 1000 mm using M20 concrete reinforced with TMT bars Fe 550 @ 6kg/ m2, slabs jointed in CM 1:3 proportion and nicely finished Including providing holes in the Cover slabs wherever necessary for easy drainage of surface water including of labour, materials, scaffolding, usage of machinery, curing, lead and lift charges etc, Complete	Sqm	270.00	1205.10	Rupees One Thousand Two Hundred Five And Paise Ten Only
35	providing 230 mm precast slab including all charges for transportaion erecting complete as per specification and as per the directions of Engineer in charge of the work	sqm	40.80	5037.00	Rupees Five Thousand Thirty Seven Only
36	Supplying and fixing M15 grade precast cement concrete Kerb stones for Roadway, Sidewalls and gutters fixed with CM 1:3 fixed and finsihed in line as per direction of Engineer in charge. 300 x 300 x 150 mm size (The cost of PCC shall be paid extra	m	1200.00	387.28	Rupees Three Hundred Eighty Seven And Paise Twenty Eight Only
37	Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfac	sqm	360.00	112.27	Rupees One Hundred Twelve And Paise Twenty Seven Only
38	Earth work in surface excavation by mechanical means for lowering & leveling the ground for all works other than foundation in all kinds of soils & upto depth not exceeding 300mm as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenances required to complete the work.	cum	4179.35	97.85	Rupees Ninety Seven And Paise Eighty Five Only
39	Construction of Embankment by excavating the available approved Gravel/ Murrum deposited at a place or borrow pits during or prior excavation with all lifts and lead, transportation to site, spreading, grading to required slope and compacting to meet the requirement complete as per specifications, including cost of labour,rolling,water,all materials,usage& all other appurtenaces required to complete the work.	cum	1236.00	488.22	Rupees Four Hundred Eighty Eight And Paise Twenty Two Only

40	Construction of Granular Sub-Base of required grading as per design mixing in a mechanical mix plant at OMC, carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per clause 401 (v) For Grading -V Material	Cum	2057.18	2561.61	Rupees Two Thousand Five Hundred Sixty One And Paise Sixty One Only
41	Construction of sub-grade and earthen shoulders with approved material obtained from borrow pits with all lifts & leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of table No. 300-2	Cum	588.65	507.79	Rupees Five Hundred Seven And Paise Seventy Nine Only
42	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver/grader in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density.	Cum	2813.63	2635.77	Rupees Two Thousand Six Hundred Thirty Five And Paise Seventy Seven Only
43	Prime Coat over WMM/WBM Providing and applying primer coat with SS1 grade Bitumen Emulsion on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70 kg/m2 using mechanical means. As per PWD SR for 2023-24 vide item no 5.1(502A (I)), Page no 31, Vol III	Sqm	9654.50	42.23	Rupees Forty Two And Paise Twenty Three Only
44	Tack coat on Bituminous surface Providing and applying tack coat with RS1 Bituminous Emulsion using emulsion pressure distributor at the rate of 0.20 kg/m2 on the prepared bituminous surface cleaned with mechanical broom Page No,31 Item No,5.3 Vol-3 SR,2023,24 KPWD	Sqm	48453.54	12.36	Rupees Twelve And Paise Thirty Six Only

45	Providing and laying Dense Graded Bituminous Macadam with 40/60 TPH capacity hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder VG-30, @ 4.0 per cent by weight of total mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 505 complete in all respects. As per PWD SR for 2023-24 vide item no 5.10 C (505A), Page no 33, Vol III	Cum	1211.34	9042.37	Rupees Nine Thousand Forty Two And Paise Thirty Seven Only
46	Providing and laying Bituminous Concrete with not less than 40/60 TPH capacity HMP using crushed aggregates of specified grading, premixed with bituminous binder VG-30 @ 4.78% Bitumen and waste plastic 8% of Bitumen of mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 507 complete in all respects Bituminous Concrete Grading i Using waste plastic	Cum	883.46	10393.73	Rupees Ten Thousand Three Hundred Ninety Three And Paise Seventy Three Only
47	Providing and constructing un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including construction joints, , primer, sealant , curing of concrete slabs for 14- days, and water finishing to lines and grade as per drawing and technical specification clause 1501 with all lead, lifts, loading & unloading charges, cost and conveyance of all materials, labour, equipments etc., complete. as per the directions of the	cum	832.50	6956.62	Rupees Six Thousand Nine Hundred Fifty Six And Paise Sixty Two Only

	Engineer-in-charge of the work.				
48	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 g/m2 area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35:2015.The finished surface to be level, uniform and free from streaks and holes.. 1. A sealing primer may be applied in advance on cement concrete pavement to ensure proper bonding. Any laitance and/or curing compound to be removed where paint is required to be applied on concrete surface. 2. Cost of painter is already included in usage charges of road marking machine As per PWD SR for 2023-24 vide item no 8.15(803), Page no 67, Vol III	Sqm	1022.38	545.90	Rupees Five Hundred Forty Five And Paise Ninety Only
49	Loading and Unloading of Stone Boulder/Stone aggregates/Sand/Kankar/Moorum.(Tipper 14 m3)	cum	6167.42	88.58	Rupees Eighty Eight And Paise Fifty Eight Only
50	Cost of Haulage Excluding Loading and Unloading Case-1 : Surfaced Road Taking output 25 tonnes load and lead 10 km = 250 t.km	t.km	92682.98	7.21	Rupees Seven And Paise Twenty One Only

51	Providing and laying in position Cement Concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) M20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	Cum	14.40	8792.13	Rupees Eight Thousand Seven Hundred Ninety Two And Paise Thirteen Only
52	Removing and resetting of precast kerb stones fixed with CM 1:3 fixed and finished in line as per direction of Engineer in charge. (The cost of PCC shall be paid extra)	m	420.00	36.05	Rupees Thirty Six And Paise Five Only
53	Construction of dry lean cement concrete Sub- base over a prepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 14:1, aggregate gradation after blending to be as per table 600-1, cement content not to be less than 140 kg/ m3 , optimum moisture content to be determined during trial length construction, concrete strength not to be less than 7 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver with electronic sensor, compacting with 8-10 t vibratory roller, finishing and curing.	Cum	652.50	5067.60	Rupees Five Thousand Sixty Seven And Paise Sixty Only
54	Construction of Embankment by excavating the available approved Gravel/ Murrum deposited at a place or borrow pits during or prior excavation with all lifts and lead, transportation to site, spreading, grading to required slope and compacting to meet the requirement complete as per specifications, including cost of labour,rolling,water,all materials,usage& all other appurtenaces required to complete the work.	Cum	2520.00	530.88	Rupees Five Hundred Thirty And Paise Eighty Eight Only

55	Providing & Laying at bottom and sides of Quarry pit Geosynthetic Clay Liner of thickness 6mm combining Geotextile outer layers with a core of bentonite clay bonded by needle punching technology including fabrication, transportation, cutting, lapping/or welding, placing in position, anchoring at the base to anchor trenches using available earth complete as per design (Including lapping and wastages), cost of materials, Labor, HOM of Machinery, loading, unloading, all Lead and Lift, all applicable Taxes etc. complete as per specifications and directions of the Engineer-in-charge of work.	sqm	4200.00	708.75	Rupees Seven Hundred Eight And Paise Seventy Five Only
56	Providing & Supplying & Laying of 1.5mm thick black HDPE texured Geomembrane in the quarry pits ,laying and joining each sheet using wedge welding machine including cost of allmachineries,accessories ,tools and materials consumables as per requirement and as perthe direction of Engineer incharge .	sqm	4200.00	645.75	Rupees Six Hundred Forty Five And Paise Seventy Five Only
57	Laying of a geotextile layer including cost of materials,labour ,machinery,HOM of machinery,loading,unloading,all lead and lifts,etc., complete as perspecifications and direction of Engineer inchargeof work.	sqm	5040.00	223.00	Rupees Two Hundred Twenty Three Only
58	Cutting and burning or disposing off Apu/Jondu from marshy areas as directed with all other ancillary operations complete.	Sqm	11572.21	10.34	Rupees Ten And Paise Thirty Four Only
59	Earth work excavation for Foundation by mechanical means for all works & depth upto 3 m, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenaces required to complete the work. In all kinds of soils Depth upto 3 m.	Cum	4688.75	112.20	Rupees One Hundred Twelve And Paise Twenty Only
60	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights,	Cum	1034.09	266.20	Rupees Two Hundred Sixty Six And Paise Twenty Only

	removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work. In all kinds of soils Depth upto 1.5 m				
61	Providing and Filling in foundation with granite / trap broken metal 100mm. And down size & with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift complete as per specifications.	Cum	205.13	2950.20	Rupees Two Thousand Nine Hundred Fifty And Paise Twenty Only
62	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver/grader in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density.	Cum	1173.90	2814.90	Rupees Two Thousand Eight Hundred Fourteen And Paise Ninety Only
63	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:3:6 (M10) Using 40 mm nominal size graded crushed coarse aggregates	Cum	328.54	6587.90	Rupees Six Thousand Five Hundred Eighty Seven And Paise Ninety Only
64	De-silting in Tank Bed/Feeder Channel/Canal in dry condition by excavating the deposited bed material and loading the same to transport vehicle (excluding cost of transportation) including cost of all machinery, labour & all necessary works as directed and complete as per specification.	Cum	55804.63	59.40	Rupees Fifty Nine And Paise Forty Only
65	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved mPWDcipal dumping ground or as approved by Engineer-in-charge to the appropriate disposal area	Cum	7396.48	400.40	Rupees Four Hundred And Paise Forty Only

66	Cost of Haulage Excluding Loading and Unloading . Case-1 : Surfaced Road .B. Taking output 18 tonne load and lead of 13 km	t.km	568904.49	8.80	Rupees Eight And Paise Eighty Only
67	Providing and fixing pre cast solid cement concrete kerb stones made out of M20 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of Nos materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete as directed by the Engineer in Charge of the work (excluding GST and Area Leading Charges)	No's	4969.00	459.00	Rupees Four Hundred Fifty Nine Only
68	Providing and laying 60mm thick factory made precast M -30 grade Cement Concrete Paver Block as per IRC SP 63:2018 & IS 15658 for Cycle Tracks & Pedestrian Footpaths of approved shape and colour, laid in required pattern and including over 30mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in charge. (WMM/WBM Base to be paid separately if necessary as per relevant technical specification)	Sqm	3913.00	1174.80	Rupees One Thousand One Hundred Seventy Four And Paise Eighty Only
69	Providing and laying in position cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:3:6 (M10) Using 20 mm nominal size graded crushed coarse aggregates	Cum	0.50	6838.70	Rupees Six Thousand Eight Hundred Thirty Eight And Paise Seventy Only

70	Providing and laying in position cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement to be paid separately) Mix 1:2:4 (M15) Using 20 mm nominal size graded crushed coarse aggregates. Add 3% for formwork over finished rate of concrete	Cum	54.00	6794.00	Rupees Six Thousand Seven Hundred Ninety Four Only
71	Providing and laying in position cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement to be paid separately) Mix 1:2:4 (M15) Using 20 mm nominal size graded crushed coarse aggregates. Add 3% for formwork over finished rate of concrete	Cum	46.19	7255.73	Rupees Seven Thousand Two Hundred Fifty Five And Paise Seventy Three Only
72	Providing and laying in-situ vibrated M-15 grade cement concrete using 40 mm down approved, clean, hard, graded aggregates for plain concrete works including cost of all materials, machinery, labour, cleaning, providing mortar layer for lift joints, batching, mixing, placing in position, levelling, vibrating, finishing, curing with all other ancillary operations complete.	Cum	15.59	6673.70	Rupees Six Thousand Six Hundred Seventy Three And Paise Seventy Only
73	Providing and laying in-situ vibrated M-15 grade cement concrete using 40 mm down approved, clean, hard, graded aggregates for plain concrete works including cost of all materials, machinery,	Cum	42.64	9102.50	Rupees Nine Thousand One Hundred Two And Paise

	labour, cleaning, providing mortar layer for lift joints, batching, mixing, placing in position, levelling, vibrating, finishing, curing with all other ancillary operations complete.				Fifty Only
74	Providing and laying in Reinforced cement concrete for all Basement & surface level works, return walls, retaining walls, sunken floors etc. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement to be paid saparatly) M20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates (10% Added on finished rate of concrete for formworkEarth retaining structures	Cum	234.00	7650.83	Rupees Seven Thousand Six Hundred Fifty And Paise Eighty Three Only
75	Providing and laying in position Reinforced cement concrete for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/ trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement, dowel bars & formwork to be paid separately) M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates (Appendix I – Additionalities for Formwork, Centering & Scaffolding,20%	Cum	47.58	9032.76	Rupees Nine Thousand Thirty Two And Paise Seventy Six Only

76	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement to be paid separately) M25 Design Mix Using 20 mm and down size graded crushed coarse aggregates (30% Added on finished rate of concrete for formwork of rcc drain)	Cum	243.82	9408.96	Rupees Nine Thousand Four Hundred Eight And Paise Ninety Six Only
77	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement to be paid separately) M25 Design Mix Using 20 mm and down size graded crushed coarse aggregates (10% Added on finished rate of concrete for formwork of earth retaining structures)	Cum	30.90	7666.56	Rupees Seven Thousand Six Hundred Sixty Six And Paise Fifty Six Only
78	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements	Cum	13.68	7238.74	Rupees Seven Thousand Two Hundred Thirty Eight And Paise Seventy Four Only

	of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement to be paid separately) M25 Design Mix Using 20 mm and down size graded crushed coarse aggregates (10% Added on finished rate of concrete for formwork of earth retaining structures)				
79	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement to be paid separately) M30 Design Mix Using 20 mm nominal size graded crushed coarse aggregates (Earth retaining structures, 20% added on finished rate of concrete for formwork bridge)	Cum	78.58	8578.68	Rupees Eight Thousand Five Hundred Seventy Eight And Paise Sixty Eight Only
80	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement to be paid separately) M30 Design Mix Using 20 mm nominal size graded crushed coarse aggregates (Earth retaining structures, 10% added on finished rate of concrete for formwork)	Cum	38.09	7863.79	Rupees Seven Thousand Eight Hundred Sixty Three And Paise Seventy Nine Only

81	Supplying, fitting and placing TMT FE 550 / 550D Steel Reinforcement including cost of all materials, machinery, labour,cleaning,straightening,cutting,bending,hooking,laping/welding joints, tying with binding wire / soft annealed steel wire and other ancilary operations complete as per drawing and technical specification.Buildings	tonne	4.28	98402.70	Rupees Ninety Eight Thousand Four Hundred Two And Paise Seventy Only
82	Supplying, fitting and placing TMT FE 550 / 550D Steel Reinforcement including cost of all materials, machinery, labour, cleaning, straightening, cutting, bending, hooking, laping/welding joints, tying with binding wire / soft annealed steel wire and other ancilary operations complete as per drawing and technical specification. All other type of structure	tonne	7.70	95076.30	Rupees Ninety Five Thousand Seventy Six And Paise Thirty Only
83	Supplying, fitting and placing TMT FE 550 / 550D Steel Reinforcement including cost of all materials, machinery,labour,cleaning,straightening,cutting,bending,hooking,laping/welding joints, tying with binding wire / soft annealed steel wire and other ancilary operations complete as per drawing and technical specification.All other type of structures	tonne	49.36	86912.10	Rupees Eighty Six Thousand Nine Hundred Twelve And Paise Ten Only
84	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with PVC Pipe 110mm outer dia at 2 kg per m2, extending through the full width of the structure with slope of 1V :20H towards drawing foce. Complete as per drawing and Technical Specifications	Mtr	24.00	262.90	Rupees Two Hundred Sixty Two And Paise Ninety Only
85	Providing ruled pointing to cursed stone masonry with lime mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost all materials, labour, usage charges of machinery, curing complete as pre specification	Sqm	27.00	328.90	Rupees Three Hundred Twenty Eight And Paise Ninety Only
86	Providing Size Stone masonry with hard stone in foundation & plinth with Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	123.72	7027.90	Rupees Seven Thousand Twenty Seven And Paise Ninety Only
87	Providing and constructing 300 mm thick size stone pitching using 200 to 250 mm size stones with pin headers at 2 per sqm set in CM 1 : 5 proportion by volume with pointing joints in CM 1 : 3 proportion by volume including cost of all materials from approved source, labour packing stone chips and mortar into joints,finishing,curing etc.,complete with all lead and lifts..	Cum	32.50	1048.30	Rupees One Thousand Forty Eight And Paise Thirty Only

88	Providing and constructing 300 mm thick size stone pitching using 200 to 250 mm size stones with pin headers at 2 per sqm set in CM 1 : 5 proportion by volume with pointing joints in CM 1 : 3 proportion by volume including cost of all materials from approved source, labour packing stone chips and mortar into joints,finishing,curing etc.,complete with all lead and lifts..	Sqm	56.60	935.00	Rupees Nine Hundred Thirty Five Only
89	Providing and constructing rockfill embankment using 300mm down graded stones and quarry spalls from approved source including cost of all materials, machinery, labour, spreading stones and spalls in layers, hand packing, wedging, finishing the surface to required slopes as per approved drawings and all other ancillary operations complete. (For Dam and Allied works)	Cum	4545.00	608.30	Rupees Six Hundred Eight And Paise Thirty Only
90	Providing and constructing dry rubble rock-toe using rubble and stone chips from approved source including cost of all materials, machinery, labour, hand packing rubble and stone chips, finishing top and sides to required slopes as per approved drawings and all other ancillary operations complete.	Cum	344.52	1369.50	Rupees One Thousand Three Hundred Sixty Nine And Paise Fifty Only
91	Providing and laying Pitching on slopes laid over prepared filter media including boulder apron laid dry in front of toe of embankment complete as per drawing and Technical specifications A.Stone/Boulder	Cum	1085.70	2103.20	Rupees Two Thousand One Hundred Three And Paise Twenty Only
92	Providing and laying Hariyala or other approved quality turfing sods for the slopes of earthen embankments over 20 mm thick sand backing including cost of all materials, machinery,labour including preparing surface, spreading sand including tamping, watering for 15 days & all necessary works as directed and complete as per specification.	Sqm	1251.80	168.30	Rupees One Hundred Sixty Eight And Paise Thirty Only
93	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations and other similar works etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m	Cum	308.37	292.60	Rupees Two Hundred Ninety Two And Paise Sixty Only
94	Providing and fixing Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar,	KG	47351.89	149.60	Rupees One Hundred Forty Nine And Paise Sixty Only

	ladder, railings, brackets, gates and similar works including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in Charge.				
95	Providing and fixing Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished seamless type tubes including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge	KG	32.00	161.70	Rupees One Hundred Sixty One And Paise Seventy Only
96	Providing and fixing Structural Steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge.	KG	3238.95	124.30	Rupees One Hundred Twenty Four And Paise Thirty Only
97	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge. (Made of G.I. wire of dia 4 mm)	Sqm	1250.00	883.30	Rupees Eight Hundred Eighty Three And Paise Thirty Only
98	Supplying and fixing of MS ornamental decorative circular type 60mm Dia ball with 4mm thick fixing over the MS base plat of size 72X72X4mm thick, welded and grinded finishing of ball including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge.	No's	317.00	198.02	Rupees One Hundred Ninety Eight And Paise Two Only
99	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two coat applied @ 0.90 ltr/10 m² over an under coat of primer applied @ 0.80 ltr/10 m² of approved brand and manufacture including preparing the surface after thorougly cleaning oil, grease, dirt and foreign matter, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.	Sqm	2598.57	152.90	Rupees One Hundred Fifty Two And Paise Ninety Only

100	Floor painting with floor enamel paint of approved brand and manufacture of required colour to give an even shade :Two coats on new work after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.	Sqm	447.20	151.80	Rupees One Hundred Fifty One And Paise Eighty Only
101	Fabricating, providing and erecting in position of MS Sq. Hallow Poles of 113 x 113 Heavy gauge of length 3000mm with MS. grill. work as per approved design and drawing of chief architect. Using 12x75mm galvanized flat for all-round frame and 16mm x 16mm galvanized-forged design with square for vertical at 150mm C/C as shown in the drawing including providing forged ornamental arrowhead at top and bottom. The work is inclusive of throughing flat, square rods, placing welding all the joints, including grinding, finishing 2 coats of anticorrosive paint over one coat of metal primer. The rate is inclusive of all materials like MS. Hollow galvanized pipe, flats, forged square rods, cost of labour for all items of work cost painting, welding, cutting, grinding with all lead and lift as per specification including loading and unloading with cost and conveyance of all materials, labour, machinery and incidental charges for the successful completion of the work as per the direction Engineer in-charge of the work.	Sqm	705.00	11073.00	Rupees Eleven Thousand Seventy Three Only
102	Fencing with G.I. barbed wire Angle iron post placed at required distance embedded in cement concrete blocks, every 15th post, last but one end post and corner post shall be strutted on both sides and end post on one side only and provided with horizontal lines and two diagonals interwoven with horizontal wires, of barbed wire weighing 9.38 kg per 100 m (minimum), between the two posts fitted and fixed with G.I. staples, turn buckles etc. complete. (Cost of posts, struts, earth work and concrete work to be paid for separately). Payment to be made per metre cost of total length of barbed wire used. With G.I. barbed wire as per the direction of engineer in charge of work	mtr	1875.00	19.80	Rupees Nineteen And Paise Eighty Only

103	Supplying S&S RCC SPUN / VIBRATED CAST PIPES (REINFORCED) pipes NP-3 Class conforming to IS:458-1988 with latest amentments using ordinary portland cement, for sanitary works and conveying to work site, rolling and lowering into trenches, laying true to line and level including loading and unloading at both destinations and jointing of pipes and specials, perfect linking of joints with jack to correct position including cost of jointing materials, i.e, rubber rings conforming to IS: 5382 for S&S RCC pipes, with all leads and lifts as directed and giving necessary hydraulic test as per ISS to the required pressure and commissioning etc. complete. (Contractor will make his own arrangements for procuring water for testing). Before the execution of the work, the contractor shall carry out the survey RCC NP3 Class pipe of 300 mm dia.	mtr	45.00	1465.20	Rupees One Thousand Four Hundred Sixty Five And Paise Twenty Only
104	Supplying S&S RCC SPUN / VIBRATED CAST PIPES (REINFORCED) pipes NP-3 Class conforming to IS:458-1988 with latest amentments using ordinary portland cement, for sanitary works and conveying to work site, rolling and lowering into trenches, laying true to line and level including loading and unloading at both destinations and jointing of pipes and specials, perfect linking of joints with jack to correct position including cost of jointing materials, i.e, rubber rings conforming to IS: 5382 for S&S RCC pipes, with all leads and lifts as directed and giving necessary hydraulic test as per ISS to the required pressure and commissioning etc. complete. (Contractor will make his own arrangements for procuring water for testing). Before the execution of the work, the contractor shall carry out the survey RCC NP3 Class pipe of 600 mm dia.	mtr	20.00	3454.00	Rupees Three Thousand Four Hundred Fifty Four Only

105	Supplying S&S RCC SPUN / VIBRATED CAST PIPES (REINFORCED) pipes NP-3 Class conforming to IS:458-1988 with latest amentments using ordinary portland cement, for sanitary works and conveying to work site, rolling and lowering into trenches, laying true to line and level including loading and unloading at both destinations and jointing of pipes and specials, perfect linking of joints with jack to correct position including cost of jointing materials, i.e, rubber rings conforming to IS: 5382 for S&S RCC pipes, with all leads and lifts as directed and giving necessary hydraulic test as per ISS to the required pressure and commissioning etc. complete. (Contractor will make his own arrangements for procuring water for testing). Before the execution of the work, the contractor shall carry out the survey RCC NP3 Class pipe of 1000 mm dia.	mtr	182.60	6020.30	Rupees Six Thousand Twenty And Paise Thirty Only
106	Providing and constructing "WIRE CUT BRICK MACHINEHOLE CHAMBERS" using Portland /Pozzolana cement, conical in shape at top, with CC 1:3:6 foundation using 40mm and down size graded metal of approved quality and with an offset of 0.15M alround the chamb Construct Brick masonry in CM 1:4, 340 mm thick, with wirecut bricks of approved quality, plaster inside and out side with CM 1:3, 12mm thick, except for the conical surface outside where the plaster thickness shall be 20mm. Slope inside to be 1:6 in the concrete towards central drain and finished smooth. Fixing of pipes in CC 1:2:4 with graded metal of 20mm and down size. Providing and fixing SFRC Machinehole frame and cover (Heavy Duty) conforming to IS:12592 with latest amendment, in CC 1:2:4. Providing and fixing footsteps made of 12mm dia. steel bars (Fe-500) with 3mm thick plastic encapsulation (IS-10910). The footsteps shall be fixed 30cms apart and on CC block embeded to masonry wall. The whole works include watering, curing, barricading, danger lighting, pouring tar over MH frame and cover, cost of tar, shoring, strutting, de-watering, engraving Machinehole number with flow direction on the inner conical surface etc. as per the drawing etc. as per technical specifications and for the following diameters and depth etc. for 1.2mm dia Constructing Brick Masonry Circular Machinehole 1.2 m internal dia. , 1.6M depth & SFRC cover & frame	No	2.00	45724.80	Rupees Forty Five Thousand Seven Hundred Twenty Four And Paise Eighty Only

107	Providing and fixing granite benches, with three line dressing, ornamental design with two groves and three bull nose finishing the sides faces of the seating slab of 75mm thickness, resting on two vertical slabs similar, ornamental dressed with peepul leaf shaped groove cutting on outer surface of the legs fixed in concrete bed including cost of all materials, transportation, labour, curing complete as per drawing and directions of Engineer-in-charge (BBMP approved rate)	No's	38.00	19050.00	Rupees Nineteen Thousand Fifty Only
108	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations and other similar works etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	Cum	1597.12	176.00	Rupees One Hundred Seventy Six Only
109	Providing new embankment abutting to existing bund to strength the existing bund using soil available in adjacent area in layers of 200 to 250 mm and compacting each layer to density control of not less than 95 percent by vibrating plate compactor or pnuematic tamper including cost of all materials, machinery, labour, picking previous layer, spreading soil in layer, breaking clods, watering, Royalty & all necessary works as directed and complete as per specification.	Cum	22382.00	216.70	Rupees Two Hundred Sixteen And Paise Seventy Only
110	Providing casing embankment using semi-pervious / pervious approved soil from borrow areas in layers of 250 to 300 mm (before compaction) including cost of all materials, machinery, labour, all other operations such as collection of soil, spreading soil in layer of specified thickness, sorting out, breaking clods, levelling, sectioning edges / sides, watering, compacting each layer to density control of not less than 95 percent or as stipulated using power roller and all other ancillary operations complete.	Cum	894.30	691.90	Rupees Six Hundred Ninety One And Paise Ninety Only
111	Providing Tile brick masonry with common burnt clay Non Modular tile bricks of class designation 5.0 conforming to IS 2690 (Part I) in superstructure above plinth level up to floor I level in cement mortar 1:6 (1 cement : 6 coarse sand) including cost of all materials, labour, scaffolding and usage charges of machinery & other incidental charges complete as per the direction of engineer incharge of work	Cum	67.20	18366.70	Rupees Eighteen Thousand Three Hundred Sixty Six And Paise Seventy Only

112	Providing 18 mm cement plaster in two coats under layer 12 mm thick cement plaster with cement mortar 1:5 (1 cement : 5 coarse sand) and a top layer 6 mm thick cement plaster with cement mortar 1:3 (1 cement : 3 coarse sand) finished rough with sponge to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	Sqm	198.08	423.50	Rupees Four Hundred Twenty Three And Paise Fifty Only
113	Providing & fixing of 2-track x 2-panel sliding windows made out of multi chambered UPVC (Matching to RAL-9016) sections and with minimum TiO2(Titanium Dioxide) at 6PHR with TPE(Thermo Plastic Elastomer) and lead free, gaskets -grey colour having isolated drainage and reinforced with Galvanized Iron profile through-out the window frame. The outer frame having an overall size of 50mm width x 42mmheight with reinforcement of 1mm thickness and Sash with overall size of 31mm X 57mm with Gi reinforcement of 1mm for the frame and 1.5 mm for the sash. Coextruded Glazing bead for fixing of glass shall be of size 21.5mm x 9.5 mm. Windows shall be provided with 5mm plain float glass, standard hardware& single point locking system with touch lock.Wall thickness of frame & sash shall be of 1.8+-0.2 mm. Maximum possible size – 1519mm x 1519mm. (The cost is inclusive of all fixtures and separate charges for minor T&P's shall not be made)	Sqm	4.77	5929.00	Rupees Five Thousand Nine Hundred Twenty Nine Only
114	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required :W.C. pan with ISI marked white solid plastic seat and lid	Each	2.00	5321.80	Rupees Five Thousand Three Hundred Twenty One And Paise Eighty Only

115	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350 mm and 340x410x265 mm sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required :One urinal basin with 5 litre white P.V.C. automatic flushing cistern	Each	2.00	4899.40	Rupees Four Thousand Eight Hundred Ninety Nine And Paise Forty Only
116	Providing and fixing 100 mm sand cast Iron grating for gully trap.	Each	8.00	51.70	Rupees Fifty One And Paise Seventy Only
117	White Vitreous China Flat back wash basin size 550x 400 mm with single 15 mm C.P. brass pillar tap	UNIT	2.00	2579.50	Rupees Two Thousand Five Hundred Seventy Nine And Paise Fifty Only
118	Providing and fixing Chorinated Poly Vinyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and making good walls) 20mm nominal OD pipes	Mtr	60.00	416.90	Rupees Four Hundred Sixteen And Paise Ninety Only
119	Providing and fixing brass bib cock of approved quality : 20 mm nominal bore	No's	10.00	335.50	Rupees Three Hundred Thirty Five And Paise Fifty Only
120	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank	Ltr's	2000.00	9.90	Rupees Nine And Paise Ninety Only

121	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work-100 mm dia	Mtr	50.00	2776.40	Rupees Two Thousand Seven Hundred Seventy Six And Paise Forty Only
122	Providing& fixing of Openable door made out of multi chambered UPVC(Matching to RAL-9016) sections and with minimum TiO2(Titanium Dioxide) at 6PHR with TPV(Thermo Plastic Vulcanized) and lead free with gaskets -grey colour having isolated drainage and reinforced with Galvanized Iron profile through-out the openable frame. The frame having overall size of 60mm x 55mm with GI reinforcement of 1mm thickness and openable sash with overall size of 60mm x 102mm and GI reinforcement of 2mm thickness. Coextruded Glazing bead for fixing of glass shall be of size 20mm x 34 mm. Windows shall be provided with 6mm plain float glass, Standard hardware with 2D/3D hinge & Multi point locking system with Handle. Wall thickness of frame & sash shall be of 2mm-2.5mm. Maximum possible size – 900mm x 2400mm.(The cost is inclusive of all fixtures and separate charges for minor T&P's shall not be made)	Sqm	7.56	6869.50	Rupees Six Thousand Eight Hundred Sixty Nine And Paise Fifty Only
123	Providing, supplying to work site,Single Phase Submersible Pump Sets of 100mm dia (4 inch) suitable for bore well confirming to IS 8034-2000 specifications,with testing of as per instructions of engineer incharge of work and latest amendments.0.50 HP/0.37kW - 5 STG(stage)	Each	1.00	11187.00	Rupees Eleven Thousand One Hundred Eighty Seven Only
124	Concealed Conduit System: Supplying heavy gauge PVC conduit pipe 25 mm dia 2 mm thick confirming to IS 2509 with suitable sizebends, metal/PVC Junction boxes, adhesive paste etc., andrunning before concreting the slab. The conduit should be tiedto the reinforcement rods by using binding wires and unusedways of junction boxes and pipe ends should be coveredusing PVC end enclosures, run with 18SWG GI fish wirewherever necessary	Mtr	100.00	85.80	Rupees Eighty Five And Paise Eighty Only
125	Supplying And Fixing Metal Fan Box with Round Hook.	No	1.00	117.00	Rupees One Hundred Seventeen

					Only
126	Supplying and fixing regular MCB distribution boards on wall/ood board / flush mounting using required clA, bolts, nuts etc., with provision for fixing suitable type capacity MCB's single phase/3 phase/single door with powder coated painting Made out of 14 SWG MS enclosure. : I - Single Door : 12 Way SP & N	Each	2.00	2049.30	Rupees Two Thousand Forty Nine And Paise Thirty Only
127	Supplying, fixing and wiring Earth Leakage Miniature Circuit Breaker (ELMCB) 240/450V upto 300mA sensitivity on existing wood/panel board. : 32-40 A 2 pole	Each	1.00	5014.90	Rupees Five Thousand Fourteen And Paise Ninety Only
128	Supplying and wiring adopting loop system in existing PVC Conduit /casing capping using 2x1.5mm2 (Phase & Neutral) & 1x1.0 mm 2 (Earth wire) FRLS multi strand PVC insulated copper wire (confirming to IS-694: and latest amendments) with a 6A flush type SP control switch shall be fixed on the existing plastic sheet/ gang box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. complete for each outlet-Medium point above 3m upto 6m from tapping point to out let via switch box	Point	30.00	416.90	Rupees Four Hundred Sixteen And Paise Ninety Only
129	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand copper wire with low conductor resistance single core in open or concealed system of wiring with specified IS 694:confirming to latest amendments.: 4 mm2	Each	100.00	69.30	Rupees Sixty Nine And Paise Thirty Only
130	Supplying 6A flush type socket and 6 A flush type SP switch either surface/flush mounting in existing gang box or in 4mm thick plastic sheet and fixing over a flush mounted wooden box and wiring using necessary capacity wires as required as per IS 1293 and IS 3654 : 6A 2 Way	Each	10.00	140.80	Rupees One Hundred Forty And Paise Eighty Only
131	Supplying And fixing/replacing of 6/16/32A electrical accessories on existing switch board. : 16A SP Switch	Each	5.00	143.00	Rupees One Hundred Forty Three Only
132	Supplying And fixing/replacing of 6/16/32A electrical accessories on existing switch board. : 16/6A combined plug and socket with control switch	Each	5.00	239.80	Rupees Two Hundred Thirty Nine And Paise Eighty Only

133	Supplying of recess mounting non integrated type LED down light 10-12W luminaire comprising of pressure decast/ extruded aluminium housing, with spring loaded false ceiling clA, LED of Power/COB with CCT 6500 degree K, CRI> 70%. efficacy >100 lumen per W, 120degree beam spread, life> 25000 burning hours and Compliance to IS10322/IEC 60598, LM 79 & LM 80. The lamp compartment is enclosed with anti glare opal diffuser which enhances the lighting level. LED's are driven by HF electronic driver integrated in a separate control gear assembly., with PF > 0.95, power loss should< 5% of lamp Wage, short circuit & open circuit protection to be integrated in the circuit, THD less than 20%, Life as per LM 79. The operating input voltage should be between 130 to 275 V. BIS Approved and Tested by NABL/CPRI accredited laboratory with 2 years Warranty against any manufacturing defect working under standard electrical condition. 10-12W	Each	12.00	1395.90	Rupees One Thousand Three Hundred Ninety Five And Paise Ninety Only
134	Providing and laying flooring and steps machine cut granite slabs 40 mm thick on cement mortar bed 1:6, 25 mm thick, and pointed witce_x005f_x005f_x005f_x005f_x005f_x0002_ ment mortar 1:3 over existing cement concrete bed , including cost of materials, mortar labour, curing complete as per specifications.	Sqm	34.50	4706.90	Rupees Four Thousand Seven Hundred Six And Paise Ninety Only
135	Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2 mm and braced with flat iron diagonals 20x5 mm size, with top and bottom rail of T-iron 40x40x6 mm, with 40 mm dia steel pulleys, complete with bolts, nuts, locking arrangement, stoppers, handles, including applying a priming coat of approved steel primer including cost of materials ,labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge.	Sqm	7.56	9103.60	Rupees Nine Thousand One Hundred Three And Paise Sixty Only

136	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate sections and other sections of approved make conforming to IS: 733 and IS:1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Polyester powder coated aluminium (minimum thickness of polyester powder coating 50 micron) including cost of materials, labour, usage charges of machinery complete as per specifications.	KG	126.00	640.20	Rupees Six Hundred Forty And Paise Twenty Only
137	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :Two coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge	Sqm	244.28	183.70	Rupees One Hundred Eighty Three And Paise Seventy Only
138	Painting on G.S. sheet with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :New work (two coats) including a coat of approved steel primer but excluding a coat of mordant solution including preparing the surface after thorougly cleaning oil, grease, dirt and foreign matter, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.	Sqm	50.00	144.10	Rupees One Hundred Forty Four And Paise Ten Only

139	Constructing brick masonry chamber of internal dimension 600x450mm and depth of 600mm (inner dimensions) with modular bricks of CD 75 in cement mortar 1:6, bed concrete 150mm thick with 1:3:6, plastering 12 mm thick with cement mortar 1:4, CC 1:2:4 coping 75mmhk for fixing CI cover & frame etc. excluding the cost of CI frame and cover	Each	2.00	5270.10	Rupees Five Thousand Two Hundred Seventy And Paise Ten Only
140	Supplying to work spot rolling, lowering and placing in position RCC perforated rings in the already excavated pit including loading and unloading at both the destinations with all lead and lift with appurtenances., complete: 1200 mmx1250 mm	Each	2.00	10498.40	Rupees Ten Thousand Four Hundred Ninety Eight And Paise Forty Only
141	Direction and Place Identification Signs upto 0.9 m2 Size Board.Providing and erecting direction and place identification retro-reflectorised sign as per IRC:67:2012 made of high intensity grade sheeting vide clause 801.3, fixed over aluminium sheeting, 2 mm thick or Aluminium composite material sheet with overall thickness of 4mm with area not exceeding 0.9 m2 fixed over back support frame of min 35 x 35 x 3mm angle mounted ona mild steel circular pipe 65 NB, firmly fixed to the ground by means of properly designed foundation with M25 grade cement concrete 45 x 45 x 60 cm, 60 cm below ground level as per approved drawing	Sqm	10.80	9911.00	Rupees Nine Thousand Nine Hundred Eleven Only

142	Supply & fixing of children multi play equipment VIVA (KPS-905A-E-PVC) : All products must be tested and certified to meet EN 1176 safety standards. The EN 1176 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The EN 1176 certificates must be in the name of a supplier who has carried out in excess of at least 100 public park projects in India either by themselves or through their dealers or contractors. These EN 1176 certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory. The equipment comprises of 4 numbers of Upright structural posts of height 2.2 m and 2 numbers of Upright Structural post of height 3.0 m are to be schedule HOT DIP Galvanized steel with a 114mm OD and 2.2mm (wall) thickness of the tubing. Two numbers of Deck of size 1.14 x 1.14m are fabricated from 2mm perforated solid punched steel. Decks are pre pressed, punched, and welded, powder coated to 2.2mm thickness or vinyl plastic coated to a thickness of 4mm. Crab Roof of size 2.7 m x 1.8 m x 0.8 m, Straight Slide of size 2.22 m x 0.82m x 1.50 m, Straight Slide of size 1.72 m x 0.82 m x 1.20 m Snake Ladder Climber of thickness Dia 38 mm , Frisbee Climber, Panels with color molded in and minimum thickness of 6 - 8mm. Exposed hardware shall be covered with ultra violet stabilized plastic safety caps as per EN1176 standards as a safety feature against protruding hardware. The rates are inclusive of all taxes, transportation charges and installation. PLAY EQUIPMENT DIMENSIONS: 5.53 m x 3.56 m x 3.60 m.	Each	1.00	1487077.00	Rupees Fourteen Lakh(s) Eighty Seven Thousand Seventy Seven Only

143	Supply & fixing of children multi play equipment ZEPHYR (KPS-307A-E-PVC) with spiral slide, monkey bar with number pannel . All products must be tested and certified to meet EN 1176 safety standards. The EN 1176 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The EN 1176 certificates must be in the name of a supplier who has carried out in excess of at least 100 public park projects in India either by themselves or through their dealers or contractors. These EN 1176 certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory. The equipment comprises of 4 numbers of Upright structural posts of height 2.47 m, 2 numbers of Upright structural posts 2.6 m and 4 numbers of Upright structural posts 4.2 m are to be schedule HOT DIP Galvanized steel with a 114mm OD and 2.2mm thickness of the tubing. Four numbers of Deck of size 1.14 x 1.14m and Staircase of size 1.5m x 0.77 m are fabricated from 2mm perforated solid punched steel. Decks are pre pressed, punched, and welded, powder coated to 2.2mm thickness or vinyl plastic coated to a thickness of 4mm. Handrail of height 2.2 m and Dia 32 mm. Frisbee Climber, Piped walls of size 2.7 m. Roof of size 1.9 m x 1.7 m x 0.77m, Spiral Slide of size 1.16 m x 1.6 m x 3.6 m, Double Slide of size 2.2 m x 1.5 m x 1.45 m, Panels with color molded in and minimum thickness of 6 - 8mm. Toprails Of Monkey Bar of size 1.8 m x 1.3 m. The rates are inclusive of all taxes, transportation charges and installation. PLAY EQUIPMENT DIMENSIONS: 6.65 m x 5.24 m x 5 m.	Each	1.00	3879753.00	Rupees Thirty Eight Lakh(s) Seventy Nine Thousand Seven Hundred Fifty Three Only

144	Supply and fixing of childern Multi Play Equipment VOYAGER (KPS-4950A-E-PVC) with double swing, curved side toddler slide with animated roof. All products must be tested and certified to meet EN 1176 safety standards. The EN 1176 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The EN 1176 certificates must be in the name of a supplier who has carried out in excess of at least 100 public park projects in India either by themselves or through their dealers or contractors. These EN 1176 certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory. The equipment comprises of 4 numbers of Upright structural posts of height 2.6 m and 4 numbers of Upright structural posts 3.05 m are to be schedule HOT DIP Galvanized steel with a 114mm OD and 2.2mm thickness of the tubing. Three numbers of Deck of size 1.14 x 1.14m and Staircase of size 1.50 m x 0.68 m are fabricated from 2mm perforated solid punched steel. Decks are pre pressed, punched, and welded, powder coated to 2.2mm thickness or vinyl plastic coated to a thickness of 4mm. Handrail of height 2.21 m and Dia 32 mm. Frisbee Climber, Piped walls of size 2.7 m, Stepped Ladder Climber of thickness Dia 38 mm, Piped walls of Height 2.7 m. Sun Roof of Dia 1.9 m and height 0.9 m , Spiral Slide of size 2.18 m x 1.63 m x 1.88 m, Straight slide of size 1.66 m x 0.93 m x 0.9 m,Panels with color molded in and minimum thickness of 6 - 8mm. Toprails Of Swing of size 3.2 m x 1.14 m thickness of 2.2 mm galvanized steel pipes. The rates are inclusive of all taxes, transportation charges and installation. PLAY EQUIPMENT DIMENSIONS: 8.24 m x 4.32 m x 4.10 m.	Each	1.00	2352362.00	Rupees Twenty Three Lakh(s) Fifty Two Thousand Three Hundred Sixty Two Only

145	SUPPLYING AND FIXING OF GAZEBO MADE OF SADARAHALLI GRANITE STONE OF SIZE NOT LESS THAN 18 FEET *18 FEET , WITH ALROUND GRANITE SEATING AND ENTRANCE STEPS WITH ALL NECESSARY TRUSS WORK TO ROOFING , ROOFING SHALL BE OF GRANITE SLAB OR MANGALORE TILE OF TYPE PORTUGUESE PATTERN OR MASTER BAMBOO OR JAPAN DUTCH TYPE OF ROOF TILES AS DIRECTED BY ENGINEER INCHARGE OF WORK . TRUSS ARE OF ISI GRADE AND ARE PAINTED WITH TWO COATS OF PRIMER AND TWO COATS OF PAINT OVER STEEL INCLUDING OF COST OF ALL LABOUR, FABRICATING, MACHINARIES, MATERIAL ETC,. INCLUDING FIXING THE GAZEBO PILLER IN CC 1:2:4 , CURING ETC., COMPLETE WITH ALL LEAD, LIFT, LOADING UNLOADING AND ANY OTHER INCIDENTAL CHARGES AND AS PER SPEC AND DIRECTION OF ENGG IN CHARGE OF WORK.	UNIT	2.00	1100000.00	Rupees Eleven Lakh(s) Only
146	SUPPLYING AND FIXING OF GAZEBO MADE OF SADARAHALLI GRANITE STONE OF SIZE NOT LESS THAN 20 FEET * 9 FEET , WITH ALROUND GRANITE SEATING AND ENTRANCE STEPS WITH ALL NECESSARY TRUSS WORK TO ROOFING , ROOFING SHALL BE OF GRANITE SLAB OR MANGALORE TILE OF TYPE PORTUGUESE PATTERN OR MASTER BAMBOO OR JAPAN DUTCH TYPE OF ROOF TILES AS DIRECTED BY ENGINEER INCHARGE OF WORK . TRUSS ARE OF ISI GRADE AND ARE PAINTED WITH TWO COATS OF PRIMER AND TWO COATS OF PAINT OVER STEEL INCLUDING OF COST OF ALL LABOUR,FABRICATING,MACHINARIES, MATERIAL ETC,. INCLUDING FIXING THE GAZEBO PILLER IN CC 1:2:4 , CURING ETC., COMPLETE WITH ALL LEAD, LIFT, LOADING UNLOADING AND ANY OTHER INCIDENTAL CHARGES AND AS PER SPEC AND DIRECTION OF ENGG IN CHARGE OF WORK.	UNIT	1.00	850000.00	Rupees Eight Lakh(s) Fifty Thousand Only

147	SUPPLYING AND FIXING OF PARGOLA MADE OF SADARAHALLI GRANITE STONE OF SIZE NOT LESS THAN 18 FEET *10 FEET , WITH ALROUND GRANITE SEATING AND ENTRANCE STEPS WITH ALL NECESSARY TRUSS WORK TO ROOFING , ROOFING SHALL BE OF GRANITE SLAB OR MANGALORE TILE OF TYPE PORTUGUESE PATTERN OR MASTER BAMBOO OR JAPAN DUTCH TYPE OF ROOF TILES AS DIRECTED BY ENGINEER INCHARGE OF WORK . TRUSS ARE OF ISI GRADE AND ARE PAINTED WITH TWO COATS OF PRIMER AND TWO COATS OF PAINT OVER STEEL INCLUDING OF COST OF ALL LABOUR, FABRICATING, MACHINARIES, MATERIAL ETC,. INCLUDING FIXING THE GAZEBO PILLER IN CC 1:2:4 , CURING ETC., COMPLETE WITH ALL LEAD, LIFT, LOADING UNLOADING AND ANY OTHER INCIDENTAL CHARGES AND AS PER SPEC AND DIRECTION OF ENGG IN CHARGE OF WORK.	UNIT	3.00	712500.00	Rupees Seven Lakh(s) Twelve Thousand Five Hundred Only
148	SUPPLYING AND FIXING OF UYYALE (SWING CHAIR) MADE OF SADARAHALLI GRANITE STONE OF SIZE NOT LESS THAN 7 FEET * , 2 FEET WIDTH COVERED WITH STONE ROOF NECESSARY TRUSS WORK TO ROOFING , ROOFING SHALL BE OF GRANITE SLAB OR MANGALORE TILE OF TYPE PORTUGUESE PATTERN OR MASTER BAMBOO OR JAPAN DUTCH TYPE OF ROOF TILES AS DIRECTED BY ENGINEER INCHARGE OF WORK . TRUSS ARE OF ISI GRADE AND ARE PAINTED WITH TWO COATS OF PRIMER AND TWO COATS OF PAINT OVER STEEL INCLUDING OF COST OF ALL LABOUR,FABRICATING,MACHINARIES, MATERIAL ETC,. INCLUDING FIXING THE GAZEBO PILLER IN CC 1:2:4 , CURING ETC., COMPLETE WITH ALL LEAD, LIFT, LOADING UNLOADING AND ANY OTHER INCIDENTAL CHARGES AND AS PER SPEC AND DIRECTION OF ENGG IN CHARGE OF WORK.	UNIT	5.00	130000.00	Rupees One Lakh(s) Thirty Thousand Only

149	Fabricating, supplying and erection of ... ms long hot dip Galvanized Octagonal hot dip Pole with BSEN 10025 grade S 355 JO steel plate for shaft, IS 2062 for base plate with door opening arrangements, including suitable boards, Bakelite sheet and MCBs as per IS specifications suitable to withstand the wind speed of 47 m/s for .....m Pole in single section and single joint welded as per IS 9595/IS10178AWS having dimensions bottom ..... mm , top.... mm with 3 mm thick, suitable base plate and 4Nos of ..... long J bolts along with template and the Pole shall be hot dip galvanized in single dipping with not less than 65micron as per ASTM-A123 and 153 etc., (excluding foundation) as per drawing appended. 3m - Top 70 mm and Bottom 130 mm dia	Each	38.00	6930.00	Rupees Six Thousand Nine Hundred Thirty Only
150	Supply of LED Streetlight luminaire with pressure die cast aluminium housingbody for optimal thermal dissipation. Lamp compartment comprising of antiglare clear diffuser with Injection moulded polycarbonate material, deliveringsuperior light output Rated life Burning Hrs 50000 hr @ LumenMaintenance of 70%, maximum light intensity should be between 60 degrees to70 degrees. CCT > 5500K, IP66 optical and electrical compartment & impactresistance of complete luminaire > IK08. Power Factor >0.9 with mains,Surge Protection- Min 5KV along with Over voltage/ Overload, short circuit/ miss-wiring protection. Compatible for pole mounting with outer dia of 40mm to50mm. Universal Voltage driver to operate wide voltage range from 100V to270V 50/60Hz application. Compliance to IS 10322/IEC 60598, LM 79 &LM 80 Adherence with RoHS. UL approved MCPCB. Top access street light with single screw to ensure ease of maintenance at the sight site location withminimized minimal tools. LED Light fixture with .....W System Powerconsumption. LED Efficiency>1301m/w, nominal CRI >75. Luminairemanufacturer should have in-house facility accredited by NABL/CPRI &any Government certified agency & Design & Development facilitycertified by ISO 9001:2008. Housing with supplier word mark /name shall be Engraved / Embossing on the die cast housing/ Body part. Warranty of 2 Yearsagainst any manufacturing defect working under standard	No	38.00	4426.40	Rupees Four Thousand Four Hundred Twenty Six And Paise Forty Only

	electrical conditions asmentioned above should be given by LED manufacturer & Cree/Nichia/Lumileds/Osram make LED Source.LED Streetlight 40W				
151	Supplying and fixing Microprocessor Based Astronomical timer Switch with using necessary bolts, nuts and washers.	Each	5.00	5327.30	Rupees Five Thousand Three Hundred Twenty Seven And Paise Thirty Only
152	Supply and Installation / Fixing / Provision of Pole box with HRC Fuse / MCB provision and suitable connector / terminal for 3 Ph/ 1 Ph connections with Loop-In & Loop- Out terminals for 10 mm2 /25 mm2 3.5 C AI/Ar/Cu/Ar Cable and branch out 2.5 mm2 2 core AI/Cu PVC Insulated cable, enclosed in a Thermoplastic, Polystyrene enclosure, which should be shock proof, safe, IP65(Weather Proof), rust proof, dust proof, water proof having Internally Embedded Gasket with provision for cable entry through IP65 Thermoplastic, polyamide glands and/or grommets.200 mm x 200 mm x 98 mm	Each	38.00	2530.00	Rupees Two Thousand Five Hundred Thirty Only
153	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand copper wire with low conductor resistance single core in open or concealed system of wiring with specified IS-694:confirming to latest amendments. .2.5 sqmm	Mtr	380.00	46.20	Rupees Forty Six And Paise Twenty Only
154	Earthing: Supplying and fixing and wiring earth electrode for grounding circuits IC cutouts and other equipments on the meter board in the pit. The pits should be filled up with equal proportion of salt and charcoal 150mm around the pipe to complete depth. The connection from the pipe to the conduits etc. is to established through GI wire of sizes as per clause 7.3.3 of IS 732 using 12mm bolts, nuts, washers and check nuts, the pipe shall have 16 through holes of 12mm dia.	Job	38.00	4125.00	Rupees Four Thousand One Hundred Twenty Five Only
155	Providing,Supplying & Laying 1.1 kV, XLPE or Heat resistant PVC insulated, PVC exutruted Inner Seath Armoured LTUG Cable as per IS-1554 (Part1) or IS-7098 Part-1, Armouring strip thickness and resistivity as per IS-3975 16 Sqmm, 4 Core, (11 GI Strips - 4 x 0.8 mm)	KG	2.51	156026.20	Rupees One Lakh(s) Fifty Six Thousand Twenty Six And Paise Twenty Only

156	PROVIDING AND SUPPLYING OF FLOATING JET FOUNTAIN IN WATER BODY : SUBMERSIBLE PUMPS 15HP , CENTRE JET WITH CROWN EFFECT UPTO 30 FEET HEIGHT-1 SET , AUTO RGB 18W LIGHTING WITH SS 304 – 8 NO. CONTROL PANEL, CABLES AND ACCESSORIES INSTALLATION ,UPS FOR CONTROL PANEL, POWER BATTERY ,PROGRAMMING & INTEGRATION- INFRASTRUCTURE ,ALL REQUIRED CABLES ETC., COMPLETE WITH ALL LEAD AND LIFT, LOADING AND UNLOADING AS PER THE DIRECTIONS OF ENGINEER IN CHARGE OF WORK	UNIT	2.00	850000.00	Rupees Eight Lakh(s) Fifty Thousand Only

SECTION 10: FORMAT OF BANK GUARANTEE FOR SECURITY DEPOSIT

To: ..... *[Name of Employer]*
…… *[address of Employer]*

WHEREAS ……. *[Name and address of Contractor]* (Hereinafter called "the Contractor") has undertaken, in pursuance of Contract No. …….. dated: …… to execute ……..*[name of Contract and brief description of Works]* (hereinafter called "the Contract");

AND WHEREAS it has been stipulated by you in the said Contract that the Contractor shall furnish you with a Bank Guarantee by a recognized bank for the sum specified therein as security for compliance with his obligations in accordance with the Contract;

AND WHEREAS we have agreed to give the Contractor such a Bank Guarantee;

NOW THEREFORE we hereby affirm that we are the Guarantor and responsible to you, on behalf of the Contractor, up to a total of Rs.……*[Amount of guarantee]* [13]_Rupees……*[in words]*, and we undertake topay you, upon your first written demand and without cavil or argument, any sum or sums within the limits of …… *[amount of guarantee]*[14] as aforesaid without your needing to prove or to show grounds or reasons for your demand for the sum specified therein.

We hereby waive the necessity of your demanding the said debt from the Contractor before presenting us with the demand.

We further agree that no change or addition to or other modification of the terms of the Contract or of the Works to be performed there under or of any of the Contract documents which may be made between you and the Contractor shall in any way release us from any liability under this guarantee, and we hereby waive notice of any such change, addition or modification.

This guarantee shall be valid until 30 days from the date of expiry of the Defects Liability Period.

Signature and seal of the guarantor _____
Name of Bank _____
Address _____
Date _____